

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	56C-02-93M	1993	4	5

Curve Data
 $\Delta = 47^\circ 25'$
 $R = 1200.00'$
 $T = 465.65'$
 $L = 888.38'$
 $Ch = 868.22'$

Estimated Quantities
 Grouted rubble paving = 44 C.Y.
 Slope stabilization = 130 C.Y.

Construct new GRP Spillway
 Spillway shall be constructed entirely within State R/W

* Construct Slope Stabilization
 See Section (A) hereon

Note: Contractor shall clear & grub the slope stabilization area prior to commencing the excavation work.

Note:
 Clearing & Grubbing, Excavation work & removals shall not be paid for separately but shall be considered incidental to pay item No. 612.0100 - GRP

STATE OF HAWAII
 DEPARTMENT OF TRANSPORTATION
 HIGHWAYS DIVISION

PLAN & DETAILS
 Kuhio Highway, Storm Damage Reconstruction
 Vicinity of Anahola Stream
 Proj. No. 56C-02-93M
 Scales: As shown Jan. 1993
 SHEET NO. 1 OF 2 SHEETS

ORIGINAL PLAN	DATE
DRAWN BY	
DESIGNED BY	
CHECKED BY	
NO.	



