1	SECTION 503 - CONCRETE STRUCTURES
2 3 4	Make the following amendments to said Section:
5 6 7	(I) Amend 503.04 – Measurement by revising lines 1201 to 1205 to read as follows:
8 9 10	"503.04 Measurement. The Engineer will not measure concrete when contracted on a lump sum basis.
11 12 13 14	The Engineer will not make deductions for the volume occupied by reinforcing steel, piles, floor drains, weepholes, timber bumpers, pipes less than eight (8) inches, conduits, or expansion joint materials.
15 16	The Engineer will consider the wingwalls to be a part of the structure."
17 18 19	(II) Amend 503.05 - Payment by revising lines 1206 to 1223 to read as follows:
20 21 22 23	*503.05 Payment. The Engineer will pay for the accepted quantities of concrete complete in place at the contract lump sum price for the pay items listed below and contained in the proposal.
24 25 26 27 28 29 30 31 32 33 34 35	The contract lump sum amount paid shall be full compensation for the concrete; for placing, curing and finishing; for furnishing materials including admixtures and cement (including extra cement added to concrete deposited under water); for furnishing and installing drains, scuppers, premolded joint fillers, joint seals, waterproofing at construction joints, waterstops, pipes and conduits; for furnishing and installing metal rockers, anchor bolts, structural shapes for expansion joints and other similar items; for timber bumpers, forms, form lining and falsework or centering, bearing pads, structural steel bearing plates; and for equipment, tools, labor, materials and incidentals necessary to complete the work. The Engineer will pay for the following pay item when included in the
36 37	proposal schedule:
38 39	Pay Item Pay Unit
40 41	Concrete for Lump Sum
42 43 44 45	The Engineer will pay for excavation and backfill for foundations in accordance with and under Section 205 – Excavation and Backfill for Bridge and Retaining Structures and Section 206 – Excavation and Backfill for Drainage Facilities."

END OF SECTION 503

46

47