

1 **SECTION 603 – CULVERTS AND STORM DRAINS**

2
3 Make the following amendments to said Section:

4
5 **(I) Amend 603.03(C)(1) - Culverts** by revising lines 106 to 108 to read as
6 follows:

7
8 “Spacing between multi-barrel culverts shall be a minimum of 18 inches or
9 0.5 the culvert width, whichever is greater. The minimum spacing shall be 1 foot
10 when placing controlled low strength material (CLSM) as backfill. Anchor the
11 culverts in such a manner that the horizontal and vertical alignment of the
12 culverts does not change.”

13
14 **(II) Amend 603.04 – Measurement** by revising lines 282 to 292 to read as
15 follows:

16
17 **“603.04 Measurement.**

18
19 **(A)** The Engineer will measure bed course material for culverts per
20 cubic yard in accordance with contract documents.

21
22 **(B)** The Engineer will measure cleaning of existing culverts on a force
23 account basis in accordance with Subsection 109.06 - Force Account
24 Provisions and Compensation and as ordered by the Engineer.”

25
26 **(III) Amend 603.05 – Payment** by revising lines 294 to 349 to read as follows:

27
28 **“603.05 Payment.** The Engineer will pay for the accepted pay items listed
29 below at the contract price per pay unit, as shown in the proposal schedule.
30 Payment will be full compensation for the work prescribed in this section and
31 contract documents.

32
33 The Engineer will pay for each of the following pay items when included in
34 the proposal schedule:

35 Pay Item	36 Pay Unit
37	
38 Bed Course Material for Culvert	Cubic Yard
39	
40 36 - Inch Reinforced Concrete Pipe, Class III	Linear Foot
41	
42 Clean Existing Culverts	Force Account”
43	
44	

45 **END OF SECTION 603**