

1       **SECTION 638 – PORTLAND CEMENT CONCRETE CURB AND GUTTER**

2  
3       Make the following amendments to said Section:

4  
5       **(I) Amend 638.04 – Measurement** by revising lines 130 to 131 to read as  
6       follows:

7  
8       **“638.04 Measurement.** The Engineer will measure curb and/or gutter, by the  
9       linear foot. The Engineer will measure along the front face of the curb at the  
10      finished grade elevation. If the Engineer measures gutter separately, the  
11      Engineer will measure gutter along the front face of the gutter. The Engineer will  
12      not make deduction in gutter length for drainage appurtenances installed such as  
13      catch basins and drop inlets.

14  
15       The Engineer will measure curb and/or gutter transition for payment as  
16      follows:

17

From	To	Measurement for Payment
Cast-in-place Curb or Precast Curb	Cast-in-place Curb and Gutter	Cast-in-place Curb and Gutter
Cast-in-place Curb and Gutter	Precast Curb and Cast-in-place Gutter	Cast-in-place Curb and Gutter
Cast-in-place Curb and Gutter Type _____	Cast-in-place Curb and Gutter Type _____	Cast-in-place Curb and Gutter 1/2 of Transition to each type
Cast-in-place Curb Type _____	Cast-in-place Curb Type _____	Cast-in-place Curb 1/2 of Transition to each type

18  
19       The Engineer will measure precast concrete drop curb and driveway curb  
20      or cast-in-place integral driveway curb and gutter under the adjacent normal curb  
21      and/or gutter.”

22  
23       **(II) Amend 638.05 – Payment** by revising lines 133 to 148 to read as follows:

24  
25       **“638.05 Payment.** The Engineer will pay for the accepted quantities of curb  
26      and/or gutter at the contract lump sum price or at the contract unit price per linear  
27      foot for each type of curb and/or gutter specified.

28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45

Payment will be full compensation for work prescribed in this section and contract documents.

The Engineer will pay for each of the following pay items when included in proposal schedule:

Pay Item	Pay Unit
Curb, Type _____	Linear Foot
Gutter, Type _____	Linear Foot
Curb and Gutter, Type _____	Linear Foot"

END OF SECTION 638