

1 **SECTION 641 – HYDRO-MULCH SEEDING**

2
3 Make the following amendments to said Section:

4
5 **(I)** Amend **Subsection 641.02(B) – Fertilizer** by revising the section from
6 line 33 to 36 to read:

7
8 **“(B) Fertilizer.** Proper fertilizer shall be used in hydro-mulch mix,
9 depending on condition of soil. Apply at rates and in amounts consistent
10 with manufacturer’s specifications. Contractor shall provide a Soil Analysis
11 Report, if requested by Engineer, and shall use report to determine
12 quantity and ratio of fertilizer for sustained growth of grass. Submit
13 recommendations from a licensed Landscape Architect when deviating
14 from the application rates and amounts above.”

15
16
17 **(II)** Amend **Subsection 641.03(A) – Seeding** by revising the first paragraph
18 from line 100 to 103 to read:

19
20 **“(A) Seeding.** Apply seeded mulch within the timeframe in Subsection
21 209.03(B) – Construction Requirements, if temporary stabilization will not
22 be utilized, after completion of slopes or portion of slope when exposed
23 face attains height of 15 feet. Notify Engineer not less than 24 hours
24 ahead of hydro-mulch seeding operation. Do not hydro-mulch until the
25 Engineer inspects and accepts areas for planting.”

26
27 **END OF SECTION 641**