<u>LEGEND</u>		<u>NOTES</u>
	— 4 each Type A Raised Pavement Markers — Type C Raised Pavement Markers @ 40'-0" o.c.	1. Layout of pavement markings and striping shall be done by the Contractor and approved by the Engineer prior to any installation work.
R - R	— 4 each Type J Raised Pavement Markers — Type D Raised Pavement Markers @ 40'-0" o.c.	2. Existing pavement markings not incorporated in the final traffic pattern shall be removed as directed by the Engineer. Costs shall be incidental to the various
	8" White Stripe with Type C Raised Pavement Markers @ 20'-0" o.c. (Tape, Type I or Thermoplastic Extrusion)	pavement marking items. 3. Raised pavement markers shall not be installed within crosswalks.
	4" Double Solid Yellow with Type D Raised Pavement Markers @ 20'-0" o.c.	4. Final locations of all signs shall be approved by the Engineer prior to any installation work.
	(Tape, Type I or Thermoplastic Extrusion) 4" Double Solid Yellow Stripes with Type H	5. Existing signs not shown on these plans shall remain as posted unless otherwise directed by the Engineer. Removal and disposal of existing signs and/or posts as designated on these plans shall be incidental to the various signing items.
	Raised Pavement Markers @ 20'-0" o.c. (Tape, Type II or Thermoplastic Extrusion)	6. Final locations of all stop lines shall be approved by the Engineer prior to installation.
	4" Yellow Edge Stripe with Type H Raised Pavement Markers @ 40'-0" o.c.	7. All pavement striping shall be as noted on the legend or plans.
	(Tape, Type II or Thermoplastic Extrusion) 4" Double Solid White Stripes with Type C Raised Pavement Markers @ 20'-0" o.c. (Tape, Type I or Thermoplastic Extrusion)	8. All preformed pavement marking tapes over existing pavement shall be applied with an approved primer as recommended by the tape manufacturer and as approved by the Engineer. The primer shall be allowed to dry to the tacky stage prior to tape application.
	Lane Change Restriction Marking — 4 each Type A Raised Pavement Markers — Type C Raised Pavement Markers @ 20'-0" o.c. — 4" White Stripe (Tape, Type I or Thermoplastic Extrusion)	9. The Contractor shall erect at the beginning of the project and at the end of the project advance construction warning signs as indicated on the plans or as directed by the Engineer The signs shall be kept in place for the duration of the project and shall be maintained by the Contractor. These signs shall be placed in addition to the required traffic control signs called for in Section 645 - Work Zone Traffic Control. The advance construction
ш	4" or 8" White Edge Stripe with Type C Raised Pavement Markers @ 40'-0" o.c. (Tape, Type II or Thermoplastic Extrusion)	warning signs shall be new and become the property of the Contractor. 10. Existing signs that are to be replaced shall not be removed until new signs are installed as replacements, or the messages are no longer necessary.
	4" White Guide Lines (Tape, Type III or Thermoplastic Extrusion except for bus bays)	11. Backing for all new regulatory and warning signs shall not be spliced.
	Transverse Median Marking (Tape, Type II or Thermoplastic Extrusion)	12. All sign panels shall conform to Section 630 of Special Provisions and the latest editions and amendments of the following FHWA publications:
7///	Transverse Shoulder Marking (Tape, Type II or Thermoplastic Extrusion)	a. "Manual on Uniform Traffic Control Devices for Streets and Highways" (MUTCD) b. "Standard Highway Signs"
	Channelizing Island or Deceleration Lane Gore (Tape, Type II or Thermoplastic Extrusion)	c. "Standard Alphabets for Highway Signs"
	Crosswalk and Stop Line. All Stop Lines	13. State Route Marker Symbols, borders, messages, arrows, symbols and shields shall conform to details as shown on the plans and as specified in the MUTCD.
	shall be 10'-0" from Crosswalk unless otherwise noted. The circled number indicates the number of lanes for payment	14. All new and relocated signs and markers installed on pipe posts, light standard or expressway sign post are to be mounted with band brackets and steel braces.
	(Tape, Type III or Thermoplastic Extrusion) Pavement Arrow (Tape, Type III or Thermoplastic	15. Removal of existing delineators and posts, as directed by the Engineer or shown on the plans, shall be considered incidental to the various signing items.
ONLY	Extrusion) Pavement Word (Tape, Type III or Thermoplastic Extrusion)	16. Removal and reinstalling existing street name signs on regulatory and warning sign post shall not be paid for separately but shall be considered incidental to the various signing items.
	 4 Each Type J Raised Pavement Markers Type D Raised Pavement Markers @ 40'-0" o.c. Type H Raised Pavement Markers (Reflective Surface facing no-passing direction) 4" Single Solid Yellow Stripe (Tape, Type I or Thermoplastic Extrusion) 	17. All Reflector Marker (RM-2) not protected by a vehicular barrier shall be mounted on a flexible delineator post unless otherwise directed by the Engineer.

Extension of Edge Line, 4" Wide x 2'-0" Long White Stripe @ 10'-0" o.c. w/Type C Markers @ 40'-0" o.c. (Tape, Type III or Thermoplastic Extrusion)

DIST. NO. PROJ. NO.

> STATE OF HAWAII DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING


LEGEND, DETAILS & NOTES


KUHIO HIGHWAY RESURFACING
Kawaihau Road to Kapaa Bridge
Federal-Aid Project No. ARR-056-1(52)


Date: March 2009

SHEET No. 71 OF 6 SHEETS


16







<u>19</u>



TYPICAL DETAIL FOR CONSTRUCTION SIGNS ON TWO LANE OR MULTILANE UNDIVIDED LOW SPEED HIGHWAY

R2-5b(XX)

24"x30"


| Type II OM (2 Each)


FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	ARR-056-1(52)	2009	20	21

Work Zone Note:

- 1. This Work Zone Sign Plan is intended for use on long-term stationary work zones/construction phases (3 days or more). All work zones or construction phases less than 3 days duration will use Traffic Control Plans shown in Section 645 of the Special Provisions.
- 2. All existing regulatory speed limit signs with posts within the work zone/project limits shall be removed and replaced with work zone speed limit sign assemblies (R2-1(XX) and R2-5b(XX) with "CONSTRUCTION AREA" and "\$250 FINE HRS 291C-104" Supplemental Signs).
- 3. Construction sign assemblies shall be installed on both the approaching and trailing ends of each work zone as shown on this plan.
- 4. Each construction warning sign and work zone speed limit assembly shall have a minimum of two (2) Type II OM. Installation of each Type II OM shall be considered incidental to Item No. 645.0100 - Traffic Control.
- 5. Upon the completion of all physical work or as directed by the Engineer, all construction signs and work zone speed limit assemblies shall be removed. All speed limit signs and posts that were existing at the start of the project within the work zone/project imits shall be restored back to their original locations and configurations.
- 6. Placement of construction signs shall not obstruct the path of pedestrians and bicyclists.
- 7. The removal and restoration of existing regulatory speed limit signs shall be considered incidental to Item No. 645.0100 Traffic Control.
- 8. The installation, maintenance and removal of work zone speed limit sign assemblies shall be paid for under Item No. 645.0100 Traffic Control.
- 9. The work zone speed limit signs shall be new and become the property of the Contractor.

TABLE I GUIDELINE FOR ADVANCE PLACEMENT OF SPEED REDUCTION SIGN R2-5b(XX)-A, CONSTRUCTION AREA SPEED LIMIT				
YY – EXISTING POSTED SPEED LIMIT (MPH)	XX - NEW CONSTRUCTION AREA SPEED LIMIT (MPH)	D-REDUCED SPEED LIMIT SIGN SPACING TO FIRST CONSTRUCTION AREA SPEED LIMIT SIGN (FEET)		
≤25	EXIST. SPEED LIMIT TO REMAIN			
30	25	100		
35	25	175		
40	30	175		






REDUCED

SPEED

\$250 FINE HRS 291C-104





HRS 291C-104

BEGIN CONSTRUCTION AREA/
WORK ZONE SPEED LIMIT

Type II OM

(2 Each)






DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION

LOW SPEED UNDIVIDED HIGHWAY <u>WORK ZONE SIGNING PLAN, NOTES#DETAILS</u>

KUHIO HIGHWAY RESURFACING Kawaihau Road to Kapaa Bridge Federal-Aid Project No. ARR-056-1(52)

Scale: Not to Scale

Date: March 2009 SHEET No. 75 OF 6 SHEETS




TYPICAL DETAIL FOR CONSTRUCTION SIGNS ON TWO LANE OR MULTILANE UNDIVIDED HIGH SPEED HIGHWAY


	FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
	HAWAII	HAW.	ARR-056-1(52)	2009	21	21


Work Zone Note:

- 1. This Work Zone Sign Plan is intended for use on long-term stationary work zones/construction phases (3 days or more). All work zones or construction phases less than 3 days duration will use Traffic Control Plans shown in Section 645 of the Special Provisions.
- 2. All existing regulatory speed limit signs with posts within the work zone/project limits shall be removed and replaced with work zone speed limit sign assemblies (R2-1(XX) and R2-5b(XX) with "CONSTRUCTION AREA" and "\$250 FINE HRS 291C-104" Supplemental Signs).
- 3. Construction sign assemblies shall be installed on both the approaching and trailing ends of each work zone as shown on this plan.
- 4. Each construction warning sign and work zone speed limit assembly shall have a minimum of two (2) Type II OM. Installation of each Type II OM shall be considered incidental to Item No. 645.0100 - Traffic Control.
- 5. Upon the completion of all physical work or as directed by the Engineer, all construction signs and work zone speed limit assemblies shall be removed. All speed limit signs and posts that were existing at the start of the project within the work zone/project imits shall be restored back to their original locations and configurations.
- 6. Placement of construction signs shall not obstruct the path of pedestrians and bicyclists.
- 7. The removal and restoration of existing regulatory speed limit signs shall be considered incidental to Item No. 645.0100 - Traffic Control.
- 8. The installation, maintenance and removal of work zone speed limit sign assemblies shall be paid for under Item No. 645.0100 Traffic Control.
- 9. The work zone speed limit signs shall be new and become the property of the Contractor.


TABLE I GUIDELINE FOR ADVANCE PLACEMENT OF SPEED REDUCTION SIGN R2-5b(XX)-A, CONSTRUCTION AREA SPEED LIMIT				
YY – EXISTING POSTED SPEED LIMIT (MPH)	XX - NEW CONSTRUCTION AREA SPEED LIMIT (MPH)	D-REDUCED SPEED LIMIT SIGN SPACING TO FIRST CONSTRUCTION AREA SPEED LIMIT SIGN (FEET)		
45	35	225		
50	40	225		
55	45	300		







LEGEND: BLACK BACKGROUND: ORANGE



LEGEND: BLACK **BACKGROUND: ORANGE**

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION

HIGH SPEED UNDIVIDED HIGHWAY

WORK ZONE SIGNING PLAN, NOTES #DETAILS KUHIO HIGHWAY RESURFACING

Kawaihau Road to Kapaa Bridge Federal-Aid Project No. ARR-056-1(52) Scale: Not to Scale

SHEET No. T6 OF 6 SHEETS

Date: March 2009