

SECTION 629 - PAVEMENT MARKINGS

Make the following amendments to said Section:

(I) Amend **Subsection 629.03(B) – Temporary Pavement Markings** by revising the third paragraph from lines 62 to 63 to read:

“Maintain and replace temporary pavement markings, flexible delineators, and barricades. ”

(II) Amend **Table 629.03 – 1 – Temporary Pavement Markings** to read as follows:

“TABLE 629.03-1 TEMPORARY PAVEMENT MARKINGS	
TYPE	PAVEMENT MARKINGS
Passing Permitted - Both Sides	Single 4-inch yellow stripe 5 feet in length spaced 20 feet on center with Type D markers spaced 40 feet on center and located on center of 5-foot length of stripe.
Passing Prohibited - Both Sides	Double solid 4-inch yellow stripes with Type D markers placed 20 feet on center on one of 4-inch yellow stripes selected by the Engineer.
Passing Permitted - One Side Only	Single continuous 4-inch yellow stripe with Type D markers placed on stripe 20 feet on center on no-passing side and single 4-inch yellow stripes 5 feet in length spaced 20 feet on center on passing side.
Lane Lines - Lane Changing Permitted	Single 4-inch yellow or white stripe 5 feet in length spaced 20 feet on center with Type C or Type D markers spaced 40 feet on center.
Lane Lines - Lane Changing Prohibited	Double solid 4-inch white stripes with Type C markers placed 20 feet on center on one of the 4-inch white stripes selected by the Engineer.
Crosswalk	Two 12-inch white transverse lines spaced 8 feet on center or as ordered by the Engineer.
Stop Line	Single 12-inch white transverse line.
Note: Paint may be used for temporary markings in areas where final paving is not complete.”	