

1 **SECTION 607 – CHAIN LINK FENCES AND GATES**

2
3 Make the following amendment to said Section:

4
5 **(I) Amend 607.03 – Construction** by adding the following after Line 103:

6
7 “Install four (4) gates along chain link fence line with locations to be
8 determined by the Engineer. Chain link gates shall be constructed per
9 Standard Plan D-03 and shall be 6’ high and 12’ feet wide.”

10
11 **(II) Amend 607.04 - Measurement** by replacing lines 105 to 106 to read:

12
13 **“607.04 Measurement.** The Engineer will measure fence by the linear foot.
14 Measurement will be along the top of the fence from outside to outside of end
15 post for each continuous run of fence.

16
17 The Engineer will measure gates per each as complete units of the size
18 and type specified in the proposal, complete in place.”

19
20 **(III) Amend 607.05 – Payment** by revising lines 108 to 115 to read as follows:

21
22 **“607.05 Payment.** The Engineer will pay for the accepted quantities of
23 fence at the contract unit price per linear foot of the types and sizes specified in
24 the proposal, complete in place.

25
26 The Engineer will pay for the accepted quantities of gate at the contract
27 unit price per each types and sizes specified in the proposal, complete in place

28
29 The Engineer will pay for following pay items when included in proposal
30 schedule:

31
32

Pay Item	Pay Unit
_____ - Feet, Chain Link Fence	Linear Foot
Chain Link Gate, _____ Feet High and _____ Feet Wide	Each”

33
34
35
36
37
38
39
40 **END OF SECTION 607**