1	SECTION 641 – HYDRO-MULCH SEEDING
2 3	Make the following amendments to said Section:
4 5 6 7	(I) Amend Subsection 641.02(B) – Fertilizer by revising the section from line 33 to 36 to read:
8 9 10 11 12 13 14	"(B) Fertilizer. Proper fertilizer shall be used in hydro-mulch mix, depending on condition of soil. Apply at rates and in amounts consistent with manufacturer's specifications. Contractor shall provide a Soil Analysis Report, if requested by Engineer, and shall use report to determine quantity and ratio of fertilizer for sustained growth of grass. Submit recommendations from a licensed Landscape Architect when deviating from the application rates and amounts above."
15 16 17	(II) Amend <b>Subsection 641.03(A)</b> – <b>Seeding</b> by revising the first paragraph from line 100 to 103 to read:
18 19 20 21 22 23 24	"(A) Seeding. Apply seeded mulch within the timeframe in Subsection 209.03(B), if temporary stabilization will not be utilized, after completion of slopes or portion of slope when exposed face attains height of 15 feet. Notify Engineer not less than 24 hours ahead of hydro-mulch seeding operation. Do not hydro-mulch until the Engineer inspects and accepts areas for planting.
25 26 27	(III) Amend Section 641.04 – Measurement, from line 173 to 174 to read as follows:
28 29 30 31	<b>641.04 Measurement.</b> The Engineer will measure Hydro-mulch seeding per square yard in accordance with the contract documents."
32 33 34	(IV) Amend Section 641.05 – Payment, from line 176 to 185 to read as follows:
35 36 37 38 39	<b>641.05 Payment.</b> The Engineer will pay for the accepted pay items listed below at the contract price per pay unit, as shown in the proposal schedule. Payment will be full compensation for the work prescribed in this section and the contract documents.
40 41	The Engineer will pay for the following pay item when included in the proposal schedule:
42 43 44	Pay Item Pay Unit
44	Hydro-mulch Seeding Square Yard"

46

47