

1 **SECTION 645 – WORK ZONE TRAFFIC CONTROL**

2
3 Make the following amendments to said Section:

4
5 **(I) Amend Subsection 645.03(B) Construction Signs** by adding the
6 following paragraphs after line 170 to read as follows:

7
8 **“(1) Sign Covers.** Use sign covers when existing signs confuse
9 the public or are in conflict with TCP signs installed. Sign covers
10 shall be commercially manufactured and accepted by the Engineer
11 before use. Sign covers shall at all times and under all conditions
12 not allow any portion of the sign being covered to be visible.
13 “Homemade” or “field made” covers shall not be used. Cover both
14 sides of the sign if both sides have symbols or words. Covering of
15 sign identification markings are not required if that is the only
16 markings on that side of the sign. Sign covers shall be
17 continuously maintained.

18
19 Removal of the existing sign in lieu of the use of sign covers
20 may be acceptable to the Engineer provided the previously
21 removed existing sign is immediately reinstalled when directed.
22 Removal of existing post(s) and mounting hardware is required if
23 not used by the new TCP sign. New mounting hardware shall be
24 used to mount the TCP signs if the existing hardware is in an
25 unacceptable condition in the opinion of the Engineer. In addition,
26 should the sign or post during storage, in the opinion of the
27 Engineer, become unacceptable or lost or stolen the Contractor
28 shall replace the sign or post with a new sign or post. Use new
29 hardware to reinstall the sign regardless whether it is an existing or
30 new sign.”

31
32 **(II) Amend Subsection 645.03(F) Lane Closures** by replacing lines 254 to
33 271 with the following:

34
35 “Lane closures shall only be allowed during the construction,
36 installation, relocation and removal of the moveable temporary rockfall
37 barrier; the removal of the existing temporary rockfall protection fence; the
38 removal of the existing portable metal barrier; cold planing; repaving and
39 installation of pavement markers, and as approved by the Engineer. The
40 installation of the moveable temporary rockfall barrier in sufficient length
41 acceptable to the Engineer, will minimize the need for lane closures during
42 construction.”

43
44 **(III) Amend Subsection 645.03(H) Advertisement** by adding the following
45 after line 394:

48
49
50
51
52
53
54

“In lieu of the advertisement(s), The Engineer may substitute the use of two portable changeable message boards and accessories at no additional cost for three days for each required advertisement.”

END OF SECTION 645