

Storm Water Pollution Prevention Plan (SWPPP)

Notice of General Permit Coverage (NGPC) File No. HIR10E029

Preparation Date 2 / 3 / 14

Table of Contents

Table of Contents.....	2
7.0 Preface.....	3
7.0.1 Notes for Contractor/HDOT Construction Personnel.....	3
7.2.1 Storm Water Team.....	4
7.2.2 Nature of Construction Activities Form C.6.....	5
7.2.3 Emergency Related Projects.....	6
7.2.4 Identification of Prime Contractor and Other Site Contractors.....	6
7.2.5 Sequence and Estimated Dates of Construction Activities.....	8
7.2.6.1 Property Boundary Maps.....	8
7.2.6.2 to 7.2.6.8 State Waters and BMP Maps.....	10
7.2.7 Construction Site Pollutants.....	11
7.2.8 –Sources of Non-Storm Water.....	13
7.2.9 –Buffer Documentation.....	14
7.2.10 Storm Water Control Measures.....	16
BMP Details.....	16
7.2.10.2 – Stabilization Practices.....	39
7.2.10.3 – Post Construction Measures.....	41
7.2.11.1 – Spill Prevention and Response Procedures.....	42
7.2.11.2 – Waste Management Procedures.....	43
7.2.12 – Procedures for Inspection, Maintenance, and Corrective Action.....	43
7.2.13 – Staff Training.....	45
7.2.14 – Documentation of Compliance with Safe Drinking Water Act Underground Injection Control (UIC) Requirements for Certain Subsurface Storm Water Controls.....	46
7.2.15 –Other State, Federal, or County Permits.....	46
7.2.16 –Other Information As Requested by the Director.....	48
7.2.17 Certification of the CWB SWPPP.....	49
7.2.18 Post-Authorization Additions to the SWPPP.....	50
7.4 Required SWPPP Modifications.....	50
SWPPP Attachments.....	52
Attachment A – Contractor/Sub-Contractor Control Maps, Property Boundary Maps, State Waters and BMP Maps, and BMP Details (SWPPP Sections 7.2.4, 7.2.6.1, 7.2.6.2 to 7.2.6.8 & 7.2.10).....	52
Attachment B – HDOT SWPPP Training Log (SWPPP Section 7.2.13).....	53
Attachment C - Construction Schedule (SWPPP Section 7.2.5).....	55
Attachment D – Subcontractor Certifications/Agreements (SWPPP Section 7.2.4).....	56
Attachment E – SWPPP Inspection Report Form (SWPPP Section 7.2.12).....	57
Attachment F – Spill Prevention and Response Procedures (SWPPP Section 7.2.11.1).....	67
Attachment G – Waste Management Procedures (SWPPP Section 7.2.11.2).....	72

<i>Attachment H – Emergency Related Projects, Departures from Manufacturer’s Specifications for Fertilizers Containing Nitrogen or Phosphorus, Buffer Documentation, Documentation of Compliance with UIC Requirements, Other State/Federal/County Permits, & Other Information as Requested by the Director (SWPPP Sections 7.2.3, 7.2.9, 7.2.14, 7.2.15, and 7.2.16).....</i>	<i>77</i>
<i>Attachment I – Corrective Action Reports.....</i>	<i>78</i>
<i>Attachment J – Post-Authorization Additions to the SWPPP</i>	<i>81</i>
<i>Attachment K – SWPPP Modification Log</i>	<i>82</i>

7.0 Preface

The following documents are referenced throughout the SWPPP:

- 1) Hawaii Administrative Rules, Chapter 11-55*
- 2) Construction Best Practices Field Manual*
- 3) Hawaii Standard Specifications for Road and Bridge Construction dated 2005 and applicable special provisions.*

7.0.1 Notes for Contractor/HDOT Construction Personnel

Items in red need to be updated by the Contractor once the project is awarded prior to construction. The Contractor shall be responsible for updating the SWPPP during construction.

Note: HDOT has permitted all outfalls and disturbed potential Contractor Staging/Storage Areas within the project limits. The Contractor may use any disturbed area acceptable to the Engineer for Staging/Storage. Staging/Storage Areas outside disturbed areas or outside the project limits may require a new NPDES submittal. See permitting requirements in Section 209 of the Special Provisions.

Outfalls 4 and 5 discharge to nutrient or sediment impaired waters. The following applies to construction areas discharging to these outfalls:

- 1) Construction BMPs shall be inspected weekly, and within 24 hours of any rainfall event of 0.25 inches or greater in a 24 hour period and daily during periods of prolonged rainfall. For more details see section 7.2.12 of this SWPPP.*
- 2) Immediately initiate and complete stabilization within 7 calendar days on areas of the site in which earth-disturbing activities have temporarily or permanently ceased. For more details see section 7.2.10.2 of the SWPPP.*