

SECTION 750 – TRAFFIC CONTROL SIGN AND MARKER MATERIALS

Make the following amendments to said Section:

(I) Amend **Subsection 750.01(A)(1) Retroreflectorization** by replacing lines 8 through 31 to read:

“(1) **Retroreflectorization.** The following shall be retroreflectorized:

(a) Background for illuminated guide signs and exit number panels ("E" designation) with ASTM D 4956 Type XI retroreflective sheeting.

(b) Background for non-illuminated guide signs and exit number panels ("D" designation) with ASTM D 4956 Type XI retroreflective sheeting.

(c) Messages, arrows, and borders of guide signs and exit number panels ("D" and "E" designations) with ASTM D 4956 Type XI retroreflective sheeting.

(d) Regulatory and warning signs, directional signs ("DIR" designation), route and auxiliary markers, shield symbols, yellow "EXIT ONLY" panels, construction warning signs, and barricade rails, completely, with Type XI retroreflective sheeting.

(e) Pedestrian, school, bicycle crossing series, completely with Type IX fluorescent yellow green retroreflective sheeting.”

(II) Amend **Subsection 750.01(B) Backing** by replacing lines 72 through 73 to read:

“Aluminum sheet shall conform to ASTM B 209, alloy 5052-H38 or 6061-T6 flat sheet.”

(III) Amend **Subsection 750.01(E) Retroreflective Sheeting Materials** by replacing lines 1126 through 1137 to read:

“(E) **Retroreflective Sheeting Materials.** Retroreflective sheeting includes white or colored sheeting having smooth outer surface.

Retroreflective sheeting shall be classified in accordance with ASTM D 4956.

The coefficient of retroreflection shall meet the minimum requirements of ASTM D 4956 for the type of reflective sheeting specified.

47 The color shall conform to the latest appropriate standard color tolerance
48 chart issued by the U.S. Department of Transportation, Federal Highway
49 Administration and to the daytime and nighttime color requirements of ASTM D
50 4956.

51
52 Test methods and procedures shall be in accordance with ASTM.

53
54 **(IV) Amend Subsection 750.02(C) Square Tube Posts** by replacing lines
55 1168 through 1172 to read:

56
57 **"750.02(C) Square Tube Posts.** Square and other tube posts shall conform to
58 ASTM A 653 for cold-rolled, carbon steel sheet, commercial quality; or ASTM A
59 787 for electric-resistance-welded, metallic-coated carbon steel mechanical
60 tubing."
61

62
63
64
65
66
67 **END OF SECTION 750**
68
69
70
71