

GENERAL NOTES:

1. Scope of Work: The scope of work shall include, but shall not be limited to, the following:
 - A. Construction of Asphalt Concrete Driveway.
 - B. Pavement striping, markings & traffic sign installation.
2. Unless otherwise specified, all construction work shall be done in accordance with these plans, all applicable sections of the Standard Specifications for Road and Bridge Construction, dated 1985, as amended, of the State Highways Division, Dept. of Transportation and the Projects Special Provisions.
3. Full compensation for all additional materials and labor, not specifically shown or called for which are necessary to complete the work, shall not be paid for separately, but shall be considered incidental to the various contract items.
4. The underground pipes, cables and/or ductlines known to exist by the Engineer from his search of the records are indicated on the plans. The Contractor shall verify the location and depth of the facilities and shall exercise proper care in excavating in the vicinity of such facilities. The Contractor shall be held liable, if as a result of his operations, damages are incurred to existing facilities, whether shown on the plans or not. All damages to existing facilities shall be repaired and/or replaced immediately in accordance with the standards and specifications of the State and/or the affected utility company or governmental agency. On any unreasonable delay by the Contractor, the State shall repair said damages and bill the Contractor for the cost of the repairs.
5. All lanes shall be open to traffic during the morning peak hours from 6:30 A.M. to 8:30 A.M., during the afternoon peak hours from 3:30 P.M. to 5:30 P.M. and during all non-working hours. One lane of traffic in each direction shall be provided for at all other times. The left turn lane from Kuhio Hwy. to Kuamoo Rd. shall not be interfered with at any time.
6. Typical sections shown on the plans are shown for representational purposes only and are not intended to depict any specific location.

7. The Contractor shall remove all silt and debris, resulting from his work, from drainage facilities, roadways and other areas. The cost incurred for any remedial action by the Engineer for removal of such silt and debris from the work area shall be payable by the Contractor.
8. The Contractor, at his own expense, shall keep the project and surrounding area free from dust nuisance. The work shall be in conformance with the air pollution control standards and regulations of the State Department of Health.
9. Pavement marking notes:
 - a. The Contractors shall be responsible for all stakout/ layout for the pavement stripings, markings, & pavement markers.
 - b. Installation of all pavement stripings, markings, & pavement markers shall be in accordance with the Standard Plans.
 - c. Edge of pavement striping shall be 4" white stripe (Thermoplastic extrusion or Tape, Type II) with Type CL raised pavement markers @ 40' on center.
 - d. Crosswalk markings and stop lines shall be thermoplastic extrusion or Tape, Type III. Raised pavement markers shall not be used within cross walk areas.
 - e. Pavement arrows shall be Tape, Type I, or thermoplastic extrusion.
10. The Contractor shall keep all construction activities under strict surveillance, management and control to avoid pollution to surface and ground water resources. All work shall be in strict accordance with all State of Hawaii & Federal water pollution laws and regulations.
11. No materials and/or equipment shall be stockpiled or stored within the highway right-of-way except at locations approved in writing by the engineer.
12. Removal of beach sand is prohibited.

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	56A-02-92	1993	3	5

DATE	_____
SURVEY PLOTTED BY	_____
DRAWN BY	_____
DESIGNED BY	_____
QUANTITIES BY	_____
CHECKED BY	_____
ORIGINAL PLAN	_____
NOTE BOOK	_____
NO.	_____

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION	
GENERAL NOTES	
KUHIO HIGHWAY SAFETY IMPROVEMENTS	
Vicinity of Coco Palms Hotel	
Project No. 56A-02-92	
SCALE: NONE	DATE: APRIL, 1991
SHEET No. 1 OF 1 SHEETS	