

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15
- 16
- 17
- 18
- 19
- 20
- 21
- 22
- 23
- 24
- 25
- 26
- 27

**(I)** Amend **Section 407.03(D) Application of Tack Coat**, by replacing lines 63 - 72 to read as follows:

Before placing HMA course, apply tack coat to contact surfaces of curbs, gutters, manholes, other structures, vertical faces of existing pavements, and exposed transverse and longitudinal edges of each course edges of each course. Apply tack coat on all surfaces that will have an asphalt pavement placed on it in an uniform, full coverage manner, e.g., no visible streaks, holidays in the application, no differences in the application rate, i.e., thickness of the tack coat. The exception to this requirement shall be surfaces that will have pavement joint adhesive applied to it.”

**ER-23(001)**  
**407-1a**

**12/9/20**