

1 Make the following Section a part of the Standard Specifications:

2  
3 **“SECTION 697 – TEMPORARY CONSTRUCTION ACCESS**

4  
5 **697.01 Description.** Temporary Construction Access to access portions of the site will  
6 be allowed. All work shall be done within the project limits. Building the access is not a  
7 requirement and is considered one possible alternative to complete the necessary work.

8  
9 **697.02 Materials.** None specified.

10  
11 **697.03 Construction Requirements.**

12  
13 (A) Temporary Construction Access calculations and drawings shall be submitted  
14 to the Engineer for approval. The calculations and drawings shall be stamped by  
15 an Engineer licensed in the State of Hawaii. The Engineer’s license shall be in  
16 the field corresponding to the work such as Structural Engineering. Construction  
17 of the Temporary Construction Access shall not begin until the Engineer has  
18 approved the calculations and drawings.

19  
20 (B) All requirements of the contract documents shall be followed. Notify the  
21 Engineer at least 2 weeks in advance of starting work on the access road.

22  
23 (C) The Temporary Construction Access shall be removed and the site restored to  
24 its original condition. The installation and removal of the Temporary  
25 Construction Access and restoration of the site shall be done within the time  
26 limits provided in the construction documents.

27  
28 **697.04 Method of Measurement.** Temporary Construction Access will be paid on a  
29 lump sum basis. Measurement for payment will not apply.

30  
31 **697.05 Basis of Payment.** The Engineer will pay for Temporary Construction Access  
32 on a contract lump sum basis. Payment will be full compensation for the work prescribed  
33 in this section and the contract documents.

34  
35 This price includes full compensation for excavation, filling, and grading; dust and  
36 erosion control, all applicable environmental regulations; using or disposing surplus and  
37 suitable material; submittals; and furnishing labor, materials, tools, equipment, and  
38 incidentals necessary to complete the work.

39  
40 The Engineer will pay for the following pay item when included in the proposal schedule.

41  
42 **Pay Item** **Pay Unit**  
43  
44 Temporary Construction Access Lump Sum

45  
46 **END OF SECTION**