

1 **SECTION 407 – TACK COAT**
2

3 Make the following amendment to said Section:
4

5 **(l)** Amend **Section 407.03(D) Application of Tack Coat**, by replacing lines
6 63 - 72 to read as follows:
7

8 “Apply tack coat on existing asphalt or concrete surface, or both, to
9 be overlayed by HMA course. Once water has evaporated from asphalt
10 emulsion, tack coat is said to have set. Place HMA overlay after tack coat
11 has set and within four hours of application. For multiple lift construction,
12 tack coat application will not be waived. Remove all deleterious material
13 to bonding before applying the tack coat to the entire surface to receive
14 the next lift.
15

16 Before placing HMA course, apply tack coat to contact surfaces of
17 curbs, gutters, manholes, other structures, vertical faces of existing
18 pavements, and exposed transverse and longitudinal edges of each
19 course edges of each course. Apply tack coat on all surfaces that will
20 have an asphalt pavement placed on it in an uniform, full coverage
21 manner, e.g., no visible streaks, holidays in the application, no differences
22 in the application rate, i.e., thickness of the tack coat. The exception to
23 this requirement shall be surfaces that will have pavement joint adhesive
24 applied to it.”
25

26 **END OF SECTION 407**
27