

1 **SECTION 705 – JOINT MATERIALS FOR CONCRETE STRUCTURES**

2
3 Make the following amendments to said Section:

4
5 **(I) Amend 705.05 Flashing Compound** to read as follows:

6
7 “Flashing compound for waterproofing of joints as specified in Standard Plan
8 B-01 shall be asphaltic mastic, asbestos free, conforming to ASTM D4586. Product
9 furnished shall adhere to damp concrete and masonry surfaces.”

10
11 **(II) Amend 705 Joint Materials for Concrete Structures** by adding the
12 following Subsection:

13
14 “705.13 **Asphalt Roll Roofing (Organic Felt)**. Asphalt roll roofing, roofing
15 felt shall conform to ASTM D6380 Type III or ASTM D224 Type III.”

16
17
18 **END OF SECTION 705**
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48