

SECTION 712 - MISCELLANEOUS

Make the following amendments to said Section:

(I) Amend 712.02 Epoxy – Resin Adhesive to read as follows:

“Epoxy-Resin Adhesive. Submit six copies of product brochures. The use of the epoxy resin adhesive shall conform to the manufacturer’s recommendations. The Contractor shall also submit a certificate of compliance from the manufacturer or supplier affirming that the proposed material conforms to ASTM C881, is able to support and carry sustained tensile (creep) loads, and is appropriate for the intended use. The color for exposed surfaces shall closely match the surrounding material.”

(II) Amend 712.04(A) Non-shrink Grout by revising the first and second paragraphs at lines 31 and 38 to read as follows:

“Non-Shrink Grout. Non-shrink grout shall be Portland cement base, prepackaged, non-metallic, ready to use grout mix and shall be applied as recommended by the manufacturer. The grout shall contain 10 grams of water-based migrating amine carboxylate corrosion inhibitor per 0.5 cubic feet when required. A manufacturer’s certificate of compliance shall be submitted.”

(III) Amend **712.04(A) Non-shrink Grout** by revising the value of expansion (percent) at age 28 days in Table 712.04-2 – Compressive Strength Requirements at line 46 to read 0.02.”

(IV) Amend 712.04(B) Epoxy Grout between lines 59 and 69 to read as follows:

“Epoxy Grout. Submit six copies of product brochures and a certificate of compliance from manufacturer or supplier affirming that proposed material conforms to ASTM C881 and is appropriate for the intended use. The epoxy grout shall be able to support and carry sustained creep tensile loads. The use of the epoxy grout shall conform to the manufacturer’s recommendations. The color of the exposed materials shall closely match the surrounding material.”

END OF SECTION 712