

1 Amend **SECTION 643 – MAINTENANCE OF EXISTING LANDSCAPE AREAS**
2 to read as follows:

3
4 **“SECTION 643 – MAINTENANCE OF EXISTING LANDSCAPE AREAS**

5
6 **643.01 Description.** This section is for maintaining the existing landscape
7 areas within the construction projects limits as directed by the Engineer.

8
9 **643.02 Materials.** None

10
11 **643.03 Construction Requirements.** The work includes:

12
13 (1) Mowing.

14
15 (2) Edging and trimming of grass along curbs, paved areas, structures
16 and around trees and shrubs.

17
18 (3) Weeding.

19
20 (4) Edging and trimming of vines and ground cover.

21
22 (5) Trimming of shrubs and trees.

23
24 (6) Clearing gutters, swales and ditches.

25
26 (7) Removing and disposing rubbish and debris, including waste
27 materials resulting from the work activities of (1) thru (6) mentioned above.

28
29 (8) Maintaining the irrigation system.

30
31 (9) Monitoring for sea turtle activity as outlined in Section 671 –
32 Protection of Endangered Species.

33
34 **643.04 Method of Measurement.** The Engineer will measure maintenance
35 of existing landscape areas within the project limits on a force account basis in
36 Accordance with Subsection 109.06 Force Account Provisions and
37 Compensation and as ordered by the Engineer.

38
39 **643.05 Duration.** The Contractor shall maintain the landscaping and
40 conduct the turtle monitoring for a duration of 12 months following the completion
41 of installation of the plants and or the Sandsaver units (whichever is finished
42 later). Payment will be full compensation for the work prescribed in this section,
43 by the Engineer, and the contract documents.

44
45 **643.06 Basis of Payment.** The Engineer will pay for the accepted pay item
46 listed below at the contract price per pay unit. Payment will be full compensation

for the work prescribed in this section, by the Engineer, and the contract documents.

The camera system will be provided by the HDOT; however, the contractor will be responsible for installing the camera in accordance with the manufacturer specifications. The contractor shall monitor the accumulation of sand and for the presence of sea turtle activity in accordance with the criteria specified in the Biological Opinion and Informal Consultation for the Proposed Kuhio Highway Emergency Shoreline Mitigation Project, Wailua Beach, Kauai, Federal-aid Project No. ER-24(004) (BO) included with these contract documents. The Contractor shall use and operate the camera and conduct the physical monitoring as specified in the BO.

The Engineer will pay for the following pay item when included in the proposal schedule:

| Pay Item | Pay Unit |
|-----------------------------------------|-----------------|
| Maintenance of Existing Landscape Areas | Force Account |

An estimated amount for the force account may be allocated in the proposal schedule under 'Maintenance of Existing Landscape Areas', but the actual amount to be paid will be the sum shown on the accepted force account records, whether this sum be more or less than the estimated amount allocated in the proposal schedule."

END OF SECTION 643