

1 **SECTION 645 - WORK ZONE TRAFFIC CONTROL**

2
3 Make the following amendments to said Section:

4
5 **(I)** Amend **645.03 Construction** from line 64 to 66 to read as follows:

6
7 “Furnish two flaggers or police officers for each location that requires work
8 zone traffic control. If TCP is included in the contract documents, furnish
9 number of flaggers or police officers indicated in TCP.”

10
11 **(II)** Amend **645.03 (B) Construction Signs** from line 162 to 169 by changing all
12 references to “Construction Signs” to read “**Work Zone Signs**”.

13
14 **(III)** Amend **Subsection 645.03 Construction** by adding this paragraph after line
15 170 to read as follows:

16
17 **“(1) Covers.** Use sign covers when existing signs confuse the public or
18 are in conflict with TCP signs installed. Sign covers shall be commercially
19 manufactured and accepted by the Engineer before use. Sign covers shall at
20 all times and under all conditions not allow any portion of the sign being
21 covered to be visible. If more than one side of the sign has words or symbols
22 cover all sides of the sign until needed. “Homemade” or “field made” covers
23 shall not be used. Covering of sign identification markings are not required if
24 that is the only markings on that side of the sign. Sign covers shall be
25 maintained.

26
27 Removal of the existing sign in lieu of the use of sign covers may be
28 acceptable to the Engineer provided the previously removed existing sign is
29 immediately reinstalled when directed. Removal of existing post(s) and
30 mounting hardware is required if not used to mount the new TCP sign. New
31 mounting hardware shall be used to mount the TCP signs if the existing
32 hardware is in an unacceptable condition in the opinion of the Engineer. In
33 addition, should the sign or post during storage, in the opinion of the
34 Engineer, become unacceptable or lost or stolen the Contractor shall replace
35 the sign or post with a new sign or post. Use new hardware to reinstall the
36 sign regardless whether it is an existing sign or new.”

37
38 **(IV)** Amend **Subsection 645.03(F) Lane Closures** by revising lines 248 to 252
39 to read as follows:

40
41 **“(F) Lane Closures.** Lane closures will be allowed only from 8:30 a.m. to
42 2:30 p.m., Monday, Tuesday, Thursday and Friday. Lane closure will be
43 allowed only from 8:30 a.m. to 1:00 p.m. on Wednesdays. Only the right lane
44 in the northbound direction will be allowed to be closed during the specified
45 times. Exceptions to lane closure hours specified require written acceptance
46 by the Engineer. No increase in contract price or contract time will be given
47 for lane closure restrictions specified.”

48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94

(IV) Amend **Subsection 645.03 (F) Lane Closures** Line 253 by changing "Oahu" to "Kauai".

(V) Amend **Subsection 645.03 (G) Advisory Signs** from Line 314 to Line 324 to read as follows:

"(G) Advisory Signs. Advisory signs are not required for this project."

(VI) Amend **Subsection 645.03 (H) Advertisement** from Line 391 to Line 392 to read as follows:

"Place advertisement for three (3) consecutive days and within one (1) week before traffic pattern changes, in publication as ordered by the Engineer. In lieu of the advertisement(s), the Engineer may substitute the use of two portable changeable message boards and accessories at no additional cost for three (3) days for each required advertisement."

(VII) Amend **Subsection 645.04 - Measurement** from line 394 to line 403 to read as follows:

"645.04 Measurement.

(A) Traffic control as specified in Subsection 645.03 – Construction including sign covers and the initial advertisement(s) will be measured on contract lump sum basis. Measurement for payment will not apply.

(B) The Engineer will measure additional police officers, additional traffic control devices, and additional advertisements, if ordered by the Engineer, on a force account basis, in accordance with Subsection 109.06 – Force Account Provisions and Compensation."

(VIII) Amend **Subsection 645.05 - Payment** from lines 405 to 428 to read:

"645.05 Payment. The Engineer will pay for the accepted traffic control, additional police officers, and additional traffic control devices, and additional advertisements at the contract price per pay unit, as shown in the proposal schedule. Payment will be full compensation for the work prescribed in this section and the contract documents.

The Engineer will pay for the following pay items when included in the proposal schedule:

Pay Item	Pay Unit
Traffic Control	Lump Sum

95 Additional Police Officers, Additional Traffic Control Devices,
96 and Additional Advertisements Force Account

97
98 An estimated amount for the force account may be allocated in the proposal
99 schedule under “Additional Police Officers, Additional Traffic Control Devices, and
100 Additional Advertisements”, but the actual amount to be paid will be the sum shown
101 on the accepted force account records, whether this sum be more or less than the
102 estimated amount allocated in the proposal schedule.

103
104 The Engineer will not pay for request submittals. The Engineer will not
105 consider claims for additional compensation of late submittals or requests by
106 Contractor.”

107
108
109
110

END OF SECTION 645