

1
2
3 **SECTION 407 – TACK COAT**
4

5 Make the following amendments to said Section:
6

7
8 **(I)** Amend **Section 407.03(D) Application of Tack Coat** from line 66 to 68
9 to read as follows:
10

11
12 “For multiple lift construction, tack coat application will not be waived.
13 Remove all deleterious material to bonding before applying the tack coat
14 to the entire surface to receive the next lift.”
15

16
17 **(II)** Amend **Section 407.03(D) Application of Tack Coat** from line 70 to 72
18 to read as follows:
19

20
21 “Before placing HMA course, apply tack coat to contact surfaces of curbs,
22 gutters, manholes, other structures, vertical faces of existing pavements,
23 and exposed transverse and longitudinal edges of each course. Apply
24 tack coat on all surfaces that will have an asphalt pavement placed on it in
25 a uniform, full coverage manner, e.g., no visible streaks, holidays in the
26 application, no differences in the application rate, i.e., the thickness of the
tack coat. The exception to this requirement shall be surfaces that will
have pavement joint adhesive applied to it which shall not require any tack
coat.”

END OF SECTION 407