

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15
- 16
- 17
- 18
- 19
- 20
- 21
- 22
- 23
- 24
- 25
- 26
- 27
- 28
- 29
- 30
- 31
- 32
- 33
- 34
- 35
- 36
- 37
- 38
- 39
- 40
- 41
- 42
- 43
- 44
- 45
- 46
- 47

**(I) Amend Subsection 619.02(H)(3) – Application Records** from lines 207 to 210 to read:

(II) Amend **Subsection 619.03(A) – Codes and Standards** from lines 262 to 264 to read:

**(1) Codes and Standards.** Perform work in accordance with applicable laws, codes, and regulations. Provide inspections and permits required by Federal, State, and local governmental authorities.

**(a)** A statement declaring at least five continuous years of experience of a scope similar to that required for the work, including installing temporary irrigation (where applicable), hydro-mulch application, soil preparation, and plant installation and establishment.

**(c)** Produce a list of completed projects similar to the scope and size of the required work to substantiate the experience. The list shall contain a minimum of five different landscape projects, excluding single-family residential landscape. A minimum of five different landscape projects shall be rated positive on a performance evaluation by the references in the list below. Names and references must be current and verifiable. Use separate sheets of paper that contain all of the following information:

- 48 1. Project name
- 49 2. Location of project (city, state)
- 50 3. Owner
- 51 4. Owner Contact (name and current phone
- 52 number)
- 53 5. Architect or Engineer Company Name
- 54 6. Architect or Engineer Contact (name and
- 55 current phone number)
- 56 7. Construction Manager (name and current
- 57 phone number)
- 58 8. Description of Project, Scope of Work
- 59 Performed
- 60 9. Total Value of Construction (including change
- 61 orders)
- 62 10. Original Scheduled Completion Date
- 63 11. Actual Date of Completion

64 **(d) Approval.** The Contractor shall submit the items  
65 under this section to the Engineer for approval prior to  
66 construction. If the applicant does not have proof of five  
67 continuous years of experience with a minimum of five  
68 completed projects similar in scope and size, the Contractor  
69 shall remove the applicant from the project upon receipt of a  
70 written notice from the Engineer. Requests to substitute an  
71 applicant will be allowed under Subsection 105.16  
72 Subcontracts.”

73  
74 **(III) Amend Subsection 619.01(H) – Planting Soil** by revising the subsection  
75 from lines 305 to 306 to read:

76  
77 **“(H) Planting Soil.** Use on-site existing soil and amend with soil  
78 amendments.”

79  
80 **(IV) Amend Subsection 619.03(I)(1) – Adding Fertilizer and Amendments**  
81 by revising the section from lines 310 to 314 to read:

82  
83 **“(1)** Uniformly distribute fertilizer and amendments over planting areas.  
84 Document if rates and amounts of fertilizer deviate from manufacturer’s  
85 specifications. Rototill top four inches of existing soil with fertilizer and

amendments to create an even planting soil mix. Rototill before installing drip irrigation system.”

**(V)** Amend **Section 619.03(N) – Planting Period** by revising the section from lines 404 to 421 to read:

**“(N) Plant Inspection.**

**(1)** An inspection shall be held at the completion of all planting operations and prior to the beginning of the Plant Establishment Period.

**(2)** The Contractor shall request the inspection in writing to the Engineer at least 7 calendar days prior to the inspection, in order that a mutually agreeable time for the inspection may be arranged.

**(3)** The Contractor and the Engineer, or their representatives shall be present at the inspection.

**(4)** The Engineer will approve the landscape work based on the installation adhering to the requirements of the Plans and these Specifications.

**(5)** All deficiencies shall be corrected, and all plantings shall be accepted by the Engineer before the issuance of a commencement date of the Plant Establishment Period.”

**(VI)** Amend **Section 619.03(T) – Plant Establishment Period** by deleting the word “nine” and replacing it with the word “three” on line 453.

**(VII)** Amend **Subsection 619.03(T)(3) – Fertilizing** by adding the following paragraph after line 478:

“Submit recommendations from a licensed Landscape Architect when deviating from the application rates and amounts above. Document if the rates and amounts of fertilizer deviate from manufacturer’s specifications.”

**(VIII)** Amend **Section 619.03(U) – Acceptance** by deleting the word “90” and replacing it with the word “30” on line 530.

**(IX)** Amend **619.05 – Payment** by revising lines 550 to 573 to read:

“Vines (Bougainvillea, Awikiwiki,	Lump Sum
Prince Kuhio, Pink Mandevilla),	
Soil Amendments, Black Cinder,	
Temporary Irrigation, and	
Plant Establishment Period	

Partial Payment Schedule for Plant Installation with Plant Establishment Period. The Engineer will pay for:

(A) 60 percent of the contract bid price upon approval of the landscape work at the first Plant Inspection.

(B) 30 percent of the contract bid price in three monthly payments of 10 percent for satisfactory progress during the Plant Establishment Period.

(C) 10 percent of the contract bid price at final acceptance of the Plant Establishment Period.”

**END OF SECTION 619**