

1       **SECTION 638 – PORTLAND CEMENT CONCRETE CURB AND GUTTER**

2  
3       Make the following amendments to said Section:

4  
5       **(I)** Amend **638.04 – Measurement** by revising lines 130 to 131 to read as  
6 follows:

7  
8       **“638.04 Measurement.** The Engineer will measure curb and/or gutter, both  
9 new and reset, by the linear foot. The Engineer will measure along the front face  
10 of the curb at the finished grade elevation. If the Engineer measures gutter  
11 separately, the Engineer will measure gutter along the front face of the gutter.  
12 The Engineer will not make deduction in gutter length for drainage  
13 appurtenances installed such as catch basins and drop inlets.

14  
15       The Engineer will measure curb and/or gutter transition for payment as  
16 follows:

17

From	To	Measurement for Payment
Cast-in-place Curb or Precast Curb	Cast-in-place Curb and Gutter	Cast-in-place Curb and Gutter
Cast-in-place Curb and Gutter	Precast Curb and Cast-in-place Gutter	Cast-in-place Curb and Gutter
Cast-in-place Curb and Gutter Type _____	Cast-in-place Curb and Gutter Type _____	Cast-in-place Curb and Gutter 1/2 of Transition to each type
Cast-in-place Curb Type _____	Cast-in-place Curb Type _____	Cast-in-place Curb 1/2 of Transition to each type

18  
19  
20       **(II)** Amend **638.05 – Payment** by revising lines 133 to 148 to read as follows:

21  
22       **“638.05 Payment.** The Engineer will pay for the accepted quantities of curb  
23 and/or gutter at the contract unit price per linear foot for each type of curb and/or  
24 gutter specified.

25  
26       Payment will be full compensation for work prescribed in this section and  
27 contract documents.  
28

29           The Engineer will pay for the following pay item when included in proposal  
30 schedule:

31		
32	<b>Pay Item</b>	<b>Pay Unit</b>
33		
34	Gutter, Type _____	Linear Foot"
35		
36		
37		

**END OF SECTION 638**