

1 **SECTION 641 – HYDRO-MULCH SEEDING**

2
3 Make the following amendments to said Section:

4
5 **(I)** Amend **Subsection 641.02(B) – Fertilizer** by revising the section from
6 line 33 to 36 to read:

7
8 **“(B) Fertilizer.** Proper fertilizer shall be used in hydro-mulch mix,
9 depending on condition of soil. Apply at rates and in amounts consistent
10 with manufacturer’s specifications. Contractor shall provide a Soil Analysis
11 Report, if requested by Engineer, and shall use report to determine
12 quantity and ratio of fertilizer for sustained growth of grass. Submit
13 recommendations from a licensed Landscape Architect when deviating
14 from the application rates and amounts above.”

15
16 **(II)** Amend **Subsection 641.03(A) – Seeding** by revising the first paragraph
17 from line 100 to 103 to read:

18
19 **“(A) Seeding.** Apply seeded mulch within the timeframe in Subsection
20 209.03(B), if temporary stabilization will not be utilized, after completion of
21 slopes or portion of slope when exposed face attains height of 15 feet.
22 Notify Engineer not less than 24 hours ahead of hydro-mulch seeding
23 operation. Do not hydro-mulch until the Engineer inspects and accepts
24 areas for planting.”

25
26 **(III)** Amend **Subsection 641.04 Measurement** by revising lines 173 to 174 to
27 read:

28
29 **“641.04 Measurement.** The Engineer will not measure Hydro-mulch seeding
30 for payment.”

31
32 **(IV)** Amend **Subsection 641.05 Payment** by revising lines 176 to 199 to
33 read:

34
35 **“641.05 Payment** The Engineer will not pay for Hydro-mulch seeding
36 separately and will consider the cost for Hydro-mulch seeding as included in the
37 Pay Item 209.0100 Installation, Maintenance, Monitoring, and Removal of BMP.
38 The cost is for the work prescribed in this section and the contract documents.”

39
40
41
42 **END OF SECTION 641**