




FED. ROAD DIST. NO.	STATE	FED-AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	NH-056-1(062)	2023	12	33




REFUGE ISLAND WITH
DETECTABLE WARNING




TRANSITION RAMP WITH DETECTABLE WARNING




SHARED CURB RAMP WITH
DETECTABLE WARNING



END OF SIDEWALK CURB RAMP WITH
DETECTABLE WARNING



DETECTABLE WARNING AT CURB RAMP




BLENDED TRANSITION
WITH DETECTABLE WARNING
Not to Scale

TYPICAL INSTALLATION OF DETECTABLE WARNINGS


Not to Scale

NOTES:

1. Detectable warnings shall be 24 inches in the direction of travel and extend the full width of the curb ramp or flush surface (does not include flares).
2. Truncated domes shall have a diameter of 0.9 inch at the bottom, a diameter of 0.4 inch at the top, a height of 0.2 inch and a center-to-center spacing of 2.35 inches measured along one side of a square arrangement.
3. Domes shall be aligned on a square grid in the predominant direction of travel to permit wheels to roll between the domes.
4. There shall be a minimum of 70 percent contrast in light reflectance between the detectable warning and an adjoining surface, or the detectable warning shall be "safety yellow".
5. The material used to provide visual contrast shall be an integral part of the detectable warning surface.
6. The detectable warning shall be located so that the edge nearest the curb line or other potential hazard is 6 to 8 inches from the curb line.



ENLARGEMENT



DOMES SECTION

DETECTABLE WARNING DETAIL

Not to Scale

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
NOTE BOOK	DRAWN BY	
DESIGNED BY	CHECKED BY	
QUANTITIES BY		
CHECKED BY		

STATE OF HAWAII DEPARTMENT OF TRANSPORTATION HIGHWAYS DIVISION	
<u>DETECTABLE WARNING DETAILS</u>	
KUHIO HIGHWAY RESURFACING Laukini Road to Kapule Highway Federal-Aid Project No. NH-056-1(062)	
Not to Scale	Date: Dec, 2022
SHEET No. 1	OF 1 SHEETS