

1                   **SECTION 634 – PORTLAND CEMENT CONCRETE SIDEWALKS**

2  
3       Make the following amendment to said Section:

4  
5       **(I) Amend Section 634.04 - Measurement** by replacing lines 60 to 61 to read:

6  
7       **“634.04       Measurement.**   The Engineer will measure Portland cement  
8       concrete sidewalks by the square yard of finished surface.

9  
10           The Engineer will measure the placement of metal grate by linear feet.”

11  
12       **(II) Amend Section 634.05 – Payment** by replacing lines 62 to 72 to read:

13  
14       **“634.05       Payment.**   The Engineer will pay for the accepted quantities of  
15       Portland cement concrete sidewalk at the contract unit price per square yard  
16       complete in place as shown in the proposal.

17  
18           The Engineer will pay for the accepted quantities of metal grate at the  
19       contract unit price per linear feet placed as shown in the proposal.

20  
21           Payment will be full compensation for work prescribed in this section and  
22       contract documents.

23  
24           The Engineer will pay for following pay item when included in proposal  
25       schedule:

26

| Pay Item                                 | Pay Unit    |
|--|-------------|
| Portland Cement Concrete Sidewalk/Island | Square Yard |
| Metal Grate                              | Linear Feet |

32

33           The Engineer will pay for excavation of unsuitable material and backfill  
34       with material acceptable to the Engineer under Section 203 – Excavation and  
35       Embankment. If no pay item exists, refer to Subsection 104.02 – Changes.”

36  
37  
38  
39  
40  
41                               **END OF SECTION 634**