2 3	Make the following amendments to said Section:
4 5 6 7	(I) Amend 503.04 – Measurement by revising lines 1201 to 1205 to read as follows:
8 9 10 11	"503.04 Measurement. The Engineer will measure the concrete by cubic yard according to the dimensions shown in the contract or as ordered by the Engineer.
12 13 14 15	The Engineer will not make deductions for the volume occupied by reinforcing steel, piles, floor drains, weepholes, timber bumpers, pipes less than eight (8) inches, conduits, or expansion joint materials."
16 17 18	(II) Amend 503.05 - Payment by revising lines 1206 to 1223 to read as follows:
19 20 21 22	*503.05 Payment. The Engineer will pay for the accepted quantities of concrete complete in place at the contract unit price per cubic yard for the pay items listed below and contained in the proposal.
223 224 225 226 227 228 229 330 331 332 333	The contract unit price paid shall be full compensation for the concrete; for placing, curing and finishing; for furnishing materials including admixtures and cement (including extra cement added to concrete deposited under water); for furnishing and installing drains, scuppers, premolded joint fillers, joint seals, waterproofing at construction joints, waterstops, pipes and conduits; for furnishing and installing metal rockers, anchor bolts, structural shapes for expansion joints and other similar items; for timber bumpers, forms, form lining and falsework or centering, bearing pads, structural steel bearing plates; and for equipment, tools, labor, materials and incidentals necessary to complete the work.
34 35	The Engineer will pay for the following pay item when included in the proposal schedule:
36 37 38	Pay Item Pay Unit
39 40	Concrete Barrier Cubic Yard
41 42 43 44 45	The Engineer will pay for excavation and backfill for foundations in accordance with and under Section 205 – Excavation and Backfill for Bridge and Retaining Structures and Section 206 – Excavation and Backfill for Drainage Facilities."
46 47	END OF SECTION 503
47	END OF SECTION 503

SECTION 503 - CONCRETE STRUCTURES

1