

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HWY-K-01-96M	1996	3	9

## GENERAL NOTES

1. *The scope of work for this project includes structural excavation for drainage system, installation of 48-inch aluminum spiral rib pipe, reinforced concrete headwall, reinforced concrete bulkhead. Type C storm drain manhole, aggregate base and asphalt pavement, mix V.*
2. *The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.*
3. *The Contractor's attention is directed to the following Sections of the Special Provisions: Subsection 107.13 - Public Convenience and Safety, Subsection 107.21 - Contractor's Responsibility for Utility Property and Services, Section 645 - Traffic Control.*
4. *At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.*
5. *The existence and location of underground utilities, manholes, monuments and structures as shown on the plans are from the latest available data but the accuracy is not guaranteed. The encountering of other obstacles during the course of the work is possible. The Contractor shall be held liable for any damages incurred to the existing facilities and/or improvements as a result of his operations.*
6. *Existing drainage system will be functional at all times during construction. Contractor is to furnish materials, equipment, labor, tools and incidentals necessary to maintain flow. This work shall be considered incidental to the various contract items.*
7. *All lanes shall be opened to traffic during the morning peak hours from 6:30 AM to 8:30 AM and during the afternoon peak hours from 3:30 PM to 5:30 PM and during off-work hours. Only one lane of traffic shall be closed at any other time.*
8. *For debris removal at Kalihiwai, the Contractor shall remove the existing guardrails to facilitate his removal operations. During all-non working hours the Contractor shall re-install the guardrails or place Type II Barricades and traffic cones where guardrails have been removed. Upon completion of the removal work the Contractor shall reinstall all guardrails and posts to the satisfaction of the Engineer. Guardrail removal and reinstallation shall not be paid for separately, but shall be considered incidental to the various contract items.*
9. *For debris disposal, the Contractor shall be responsible for obtaining all permits and approvals necessary for disposal of the materials. The Contractor shall include in his bid the cost of all permits, tipping fees, etc., necessary for disposal of the materials.*
10. *The Contractor shall remove all dead trees, cut tree trunk & branches, loose vegetation, etc., that are within the debris removal limits shown on the plans.*
11. *The Contractor shall erect at the beginning of the project and at the end of the project advance construction warning signs as indicated on the plans or as directed by the Engineer for the duration of the highway project and shall be maintained by the Contractor. These signs shall be placed in addition to the required traffic control signs called for in Section 645 - Traffic Control. The advance construction warning signs shall be new and become the property of the State. The Contractor shall remove, clean, and deliver the signs and posts to the Kauai Baseyard or as directed by the Engineer at the end of the project. The advance construction warning signs shall be paid under Item No. 621.7100, Construction Sign with posts.*

ORIGINAL PLAN	SURVEY PLOTTED BY _____ DATE _____
NOTE BOOK Vol	DRAWN BY <u>Sankuwa</u>
	TRACED BY _____
	DESIGNED BY <u>Sankuwa</u>
	QUANTITIES BY _____
	CHECKED BY _____

STATE OF HAWAII  
DEPARTMENT OF TRANSPORTATION  
HIGHWAYS DIVISION

**GENERAL NOTES**

*(Old) Kuhio Highway*  
*Storm Damage Repairs at Princeville*  
*and*  
*Kuhio Highway (24.8±)*  
*Debris Removal at Kalihiwai*  
*PROJECT NO. HWY-K-01-96M*

Scale: None Date: April, 1996

SHEET No. 1 OF 1 SHEETS