

ORIGINAL
PLAN
SURVEY PLOTTED BY
DATE
DRAWN BY
DESIGNED BY
CHECKED BY

TRAFFIC SIGN SUMMARY								
SIGN NO.	MESSAGE	QUANTITY						
		10 SQ. FT. OR LESS				GREATER THAN 10 SQ. FT.		
		W/POST		W/O POST		W/POSTS		W/O POST
		EXIST.	NEW	EXIST.	NEW	EXIST.	NEW	
M4-11					3			
M4-12					2			
R1-1	STOP	17						
R1-2	YIELD	5						
R2-1(25)	SPEED LIMIT 25						3	
R2-1(35)	SPEED LIMIT 35						6	
R2-5b(25)	REDUCED SPEED 25						1	
R3-2(L)		1				1		
R3-2a	NO LEFT TURN			1				
R3-5(R)		2						
R3-7(L)	LEFT LANE MUST TURN LEFT	1						
R3-9b	CENTER LANE  ONLY	11		2				
R3-40L		3						
R3-8aL		1						
R7-107		1						
R7-107a		4						
R7-201a					17			
R8-3a		17	14					
R8-3ae			8					
R8-3ae(l)			3					
R8-3ae(r)			3					
R9-3a		2						
R10-10	DO NOT BLOCK INTERSECTION	1						
R10-12	LEFT TURN YIELD ON GREEN ●	4						
R15-1	UNLAWFUL TO LITTER \$1000 FINE	1						
R16-1	BUCKLE UP  IT'S THE LAW		1					
S1-1			1					
S2-1			2					
W1-6(L)		1						
W1-7		1						
W3-3		1						
W3-3a	SIGNAL AHEAD			1				
W4-2	LEFT LANE ENDS		1					
W4-3		2						
W9-1			1					
W11-2		5	5					
W14-1	DEAD END	1						
X1-1	NO DIVING FROM BRIDGE	1						
X1-2	END CONTR-FLOW	1						
X1-3	CONTRA-FLOW	1						
X1-4	SCHOOL BUS STOP	2						
X1-5	PEDESTRIANS PROHIBITED	2						
	TOTAL	89	39	4	22	1	10	0

NOTE: Bold letters denotes new signs to be installed on this project.

CONSTRUCTION SIGN SUMMARY			
SIGN NO.	MESSAGE	W/POSTS	W/O POST
CG20-2	END CONSTRUCTION	2	
CW20-1d	ROAD CONSTRUCTION AHEAD	3	
TOTAL		5	0

ROUTE MARKER SUMMARY					
SIGN ASSEMBLY	SIGN NO. AND MESSAGE	TYPE A ASSEMBLY		TYPE B ASSEMBLY	
		W/POST	W/O POST	W/POST	W/O POST
SRM-1	M3-4  M1-6(56) 	1			
SRM-2	M1-6(580)  M1-6(56)  M6-1(L)  M6-3 			1	
SRM-3	M2-1  M1-6(580) 	2			
SRM-4	M1-6(56)  M1-6(580)  M6-3  M6-1(R) 			1	
TOTAL		3	0	2	0

REFLECTOR MARKER SUMMARY					
TYPE	QUANTITY				
	W/O POST		W/STEEL POST		W/FLEXIBLE POST
	YELLOW	WHITE	YELLOW	WHITE	WHITE
RM-1					20
RM-3	157		15		
RM-4			8		
TYPE II OBJECT MARKER	140		5		

DESTINATION SIGN SUMMARY				
SIGN NO.	MESSAGE	SIZE	NEW PANEL AREA (SQ. FT.)	
			W/O POST	W/POSTS
D-1	 KAPAA 3 mi. HANALEI 24 mi. 39 km.  OPAEKAA 2 mi. FALLS 3 km.	7'-0" x 5'-0"		35
D-2	 KAPAA 3 mi. HANALEI 24 mi. 39 km.  OPAEKAA 2 mi. FALLS 3 km.	7'-0" x 4'-6"		31.5
D-3	 KAPAA 3 mi. HANALEI 24 mi. 39 km.  OPAEKAA 2 mi. FALLS 3 km.	7'-0" x 4'-0"		28
TOTAL				94.5

MILEPOST MARKER SUMMARY		
SIGN NO. AND MESSAGE	QUANTITY	
	BI-DIRECTIONAL W/POST	W/O POST
D10-2 0 D10-7 580	1	
D10-2 6 D10-7 56	1	
D10-2 7 D10-7 56	1	
D10-2 8 D10-7 56	1	
TOTAL	4	0

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

TRAFFIC SUMMARIES

KUHIO HIGHWAY RESURFACING

WAILUA TO KAPAA

Fed. Aid Proj. No. STP-056-1(37)

Date: April, 1995