

Amend **Section 614 - Standard Street Survey Monuments** to read as follows:

"SECTION 614 - STANDARD STREET SURVEY MONUMENTS

614.01 Description. This work includes furnishing and installing, reconstructing, and/or adjusting standard street survey monuments according to the contract.

614.02 Materials.

(A) **Concrete.** Concrete shall be Class A and shall conform to Section 601 - Structural Concrete. The Contractor may hand mix the concrete.

(B) **Pin.** The pin for marking the survey point shall be of brass. Burr or feather the pin for anchorage in the concrete.

(C) **Pipe.** Pipe shall be zinc-coated standard weight pipe conforming to ASTM A 120.

(D) **Castings.** Cast iron frames and covers shall conform to Subsection 713.09 - Gray Iron Castings. The bearing faces of the frames and covers shall be such that the cover shall lie flat in normal position in the ring.

614.03 Construction Requirements. Set each monument carefully according to the details shown in the contract and in the exact location designated. Set the casting or frame and cover secure and flush with the finished grade of the road.

These provisions shall apply equally for reconstructing and/or adjusting survey monuments. In addition, clean the metal parts salvaged for reuse of foreign matter before reinstallation.

614.04 Method of Measurement. The Engineer will measure furnishing and installing, reconstructing, and/or adjusting standard street survey monuments per each complete in place.

614.05 Basis of Payment. The Engineer will pay for the accepted furnishing and installing, reconstructing, and/or adjusting standard street survey monuments at the contract unit price per each.

The price includes full compensation for excavating; backfilling; restoring to original condition; zinc-coating; and furnishing labor, materials, equipment, tools, and incidentals necessary to complete the work.

The Engineer will make payment under:

Pay Item	Pay Unit
Standard Street Survey Monuments	Each
Reconstructing Standard Street Survey Monuments	Each
Adjusting Standard Street Survey Monuments	Each"

END OF SECTION