

Amend **Section 650 - Wheelchair Ramps** to read as follows:

"SECTION 650 - CURB RAMPS

650.01 Description. This section is for constructing curb ramps for the physically handicapped at existing or new sidewalk locations according to the contract.

650.02 Materials. Materials shall conform to the following:

Bed Course Material for Sidewalks and Curbing	703.16(A)
Joint Fillers	705.01
Reinforcing Steel	709.01

Concrete shall conform to Section 601 - Structural Concrete and shall be Class B.

Materials will be subject to inspection for acceptance as to condition at the latest practicable time the Engineer has the opportunity to check for compliance before or during incorporation of materials in the work.

650.03 Construction Requirements. Subsection 608.03(A) - Concrete Sidewalk and below shall apply to curb ramp construction requirements.

If the abutting sidewalk shows reinforcement, the Contractor shall similarly reinforce the curb ramp.

The Contractor shall require construction joint if the curb ramps join existing or new sidewalks and if curb ramp aprons abut drop curbs or gutters.

Demolition of existing curb and sidewalk shall conform to Section 202 - Removal of Structures and Obstructions.

Special drop curbs for curb ramps shall conform to Section 609 - Curb and/or Gutter.

The face of special drop curbs shall conform to the face of abutting curbs.

The profiles of curb ramps shall be such that their lower points conform to the grade of abutting edge of pavement or inverts of adjacent gutters, as applicable.

650.04 Method of Measurement. The Engineer will measure curb ramps per each complete in place.

650.05 Basis of Payment. The Engineer will pay for the accepted curb ramps at the contract unit price per each.

The price includes full compensation for demolishing; excavating; backfilling; installing reinforcing steel, concrete expansion joint materials, construction joints, special drop curbs, and bed course material; and furnishing labor, materials, equipment, tools, and incidentals necessary to complete the work.

The Engineer will make payment under:

Pay Item	Pay Unit
Curb Ramp No. _____	Each"

END OF SECTION