

## **SECTION 704 - MASONRY UNITS**

Make the following amendment to said Section:

(I) Amend **704.01 Clay or Shale Brick** to read as follows:

**"704.01 Clay or Shale Brick.** Clay or shale bricks shall conform to AASHTO M 91, Grade SM."

(II) Add the following:

**"704.03 Hollow Concrete Masonry Units.** Hollow concrete masonry units shall conform to the requirements of ASTM C90, Grade N-11, 'Hollow Load Bearing Concrete Masonry Units'.

Units shall be two core type, eight inch normal height, 16 inch normal length, and width as indicated on the plans. All units shall be sound, free of cracks, straight and true. Units shall be either steam-cured or cured under atmospheric conditions for a minimum of 30 days. Linear drying shrinkage shall not exceed 0.065 percent in accordance with ASTM C426 C90."

**END OF SECTION**