

1 Make the following Section a part of the Standard Specifications:
2

3 **"SECTION 210 - DRESSING OF SHOULDER**
4

5 **210.01 Description.** This work includes shaping, grading, filling, and
6 compacting the unpaved shoulders according to the contract, in conformity with
7 the lines, grades, and cross-sections shown on the plans or as specified by the
8 Engineer.
9

10 **210.02 Materials.** Use suitable materials from roadway excavation, including
11 topsoil and base material salvaged from this project. Consider asphalt concrete
12 removed from cold planing, reconstruction and roadway excavation as surplus
13 excavation material. Dispose of them as specified in Section 203 – Roadway
14 Excavation. Use additional materials from borrow or as specified by the
15 Engineer at no cost to the State.
16

17 **210.03 Construction Requirements.** Immediately shape, grade, and
18 compact the shoulders after the completion of or in conjunction with the
19 resurfacing of the pavement.
20

21 Compact all shoulder material placed uniformly and thoroughly by a roller
22 weighing no less than three tons. Finish the shoulders and slopes, including
23 ditches where necessary, to a reasonably smooth and uniform surface. The
24 Engineer will not permit excessive variations in the elevations or alignment of the
25 shoulders from the plan. Correct such variations to preserve a neat and uniform
26 appearance.
27

28 Correct the irregularities in the surface, if any, resulting from grading and
29 other operations to prevent formation of depressions or water pockets.
30 Similarly, repair any damage to the surface or pavement due to the Contractor's
31 operations at no cost to the State according to the contract and as specified by
32 the Engineer.
33

34 Provide the Engineer with a copy of the written agreement with any
35 property owner from whose property the borrow material is to be obtained or on
36 which the excess excavation is to be disposed.
37

38 **210.04 Method of Measurement.** The Engineer will not measure dressing
39 of shoulders for payment.
40

41 **210.05 Basis of Payment.** The Engineer will not pay for dressing of
42 shoulders separately and will consider the cost for dressing of shoulders as
43 included in the contract prices of the various contract items. The cost is for the
44 work prescribed in this section and the contract documents."
45
46

47 **END OF SECTION 210**
48