

1 Amend **Section 621 - Traffic Control Signs** to read as follows:

2
3 **"SECTION 621C - MARKERS**

4
5 **621.01 Description.** This section describes furnishing and installing reflector,
6 object, and milepost markers and post.

7
8 **621.02 Materials.**

9
10 Reflector Marker 712.21

11
12 Flexible Delineator Post 712.51

13
14 Fasteners for Signs 713.12

15
16 **621.03 Construction Requirements.**

17
18 **(A) Marker Posts.** Set marker posts plumb. Provide marker posts
19 of the following type:

20
21 **(1) Metal Posts.** Zinc-coat metal posts. Provide 1.12 pounds
22 per foot flanged channel posts or 1.5 inch, 12 or 14 gauge square
23 tube posts.

24
25 **(2) Flexible Posts.** Provide flexible post.

26
27 **(B) Markers.**

28
29 **(1) Reflector Marker.** Provide reflector marker of the following
30 type:

31
32 **(a)** RM-1, RM-2, and RM-3 reflector markers conforming
33 to the following:

34
35 **(1)** Type III or IV retroreflective sheeting markers,

36
37 **(2)** Glass sphere reflector markers with 4 - inch by
38 5 - inch reflector units, or

39
40 **(3)** Plastic prismatic reflector markers with 3 inch
41 diameter reflector units.

42
43 **(b)** RM-4 reflector marker conforming to Type III or IV
44 retroreflective sheeting marker.

45
46 **(c)** RM-9 reflector marker conforming to the following:

(1) Nine 3-inch round amber plastic prismatic reflectors fastened with blind rivets to yellow Type III or IV retroreflective sheeting marker, or

(b) Yellow Type III or IV retroreflective sheeting marker.

(2) **Type II Object Marker.** Conform reflective sheeting material for Type II object markers to Subsection 712.20(C)(4) - Type III or IV Retroreflective Sheeting.

621.04 Method of Measurement. Reflector marker, mile post marker, and object marker will be paid on a lump sum basis. Measurement for payment will not apply.

621.05 Basis of Payment. The Engineer will pay for the accepted pay items listed below on a contract lump sum basis as shown in the proposal schedule. Payment will be full compensation for the work prescribed in this section and the contract documents.

The Engineer will pay for each of the following pay item when included in the proposal schedule:

Pay Item	Pay Unit
Reflector Marker _____	Lump Sum
Mile Post Marker with Post (Bi-Directional)	Lump Sum
Mile Post Marker _____	Lump Sum
Type II Object Marker	Lump Sum"

END OF SECTION 621C