

1 **SECTION 645 - WORK ZONE TRAFFIC CONTROL**

2
3 Make the following amendments to said Section:

4
5 **(I)** Amend **Subsection 645.03 Construction** by adding this paragraph after line
6 170 to read as follows:

7
8 **“(1) Covers.** Use sign covers when existing signs confuse the public or
9 are in conflict with TCP signs installed. Sign covers shall be commercially
10 manufactured and accepted by the Engineer before use. Sign covers shall at
11 all times and under all conditions not allow any portion of the sign being
12 covered to be visible. If more than one side of the sign has words or symbols
13 cover all sides of the sign until needed. “Homemade” or “field made” covers
14 shall not be used. Covering of sign identification markings are not required if
15 that is the only markings on that side of the sign. Sign covers shall be
16 maintained.

17
18 Removal of the existing sign in lieu of the use of sign covers may be
19 acceptable to the Engineer provided the previously removed existing sign is
20 immediately reinstalled when directed. Removal of existing post(s) and
21 mounting hardware is required if not used to mount the new TCP sign. New
22 mounting hardware shall be used to mount the TCP signs if the existing
23 hardware is in an unacceptable condition in the opinion of the Engineer. In
24 addition, should the sign or post during storage, in the opinion of the
25 Engineer, become unacceptable or lost or stolen the Contractor shall replace
26 the sign or post with a new sign or post. Use new hardware to reinstall the
27 sign regardless whether it is an existing sign or new.”

28
29 **(II)** Amend **Subsection 645.03 (F) Lane Closures** Line 253 by changing "Oahu"
30 to Kauai".

31
32 **(III)** Amend **Subsection 645.03 (G) Advisory Signs** from Line 314 to Line 324 to
33 read as follows:

34
35 “Advisory signs are not required for this project.”

36
37
38 **END OF SECTION 645**