SECTION 634 – PORTLAND CEMENT CONCRETE SIDEWALKS

Make the following amendment to said Section:

(I) Amend **Section 634.04 - Measurement** by replacing lines 60 to 61 to read:

"**634.04 Measurement.** The Engineer will measure Portland cement concrete sidewalks by the square yard of finished surface."

(II) Amend **Section 634.05 – Payment** by replacing lines 62 to 72 to read:

"**634.05 Payment.** The Engineer will pay for the accepted quantities of Portland cement concrete sidewalk at the contract unit price per square yard complete in place as shown in the proposal.

Payment will be full compensation for work prescribed in this section and contract documents.

The Engineer will pay for following pay item when included in proposal schedule:

Pay Item	**Pay Unit**
Portland Cement Concrete Sidewalk	Square Foot

The Engineer will pay for excavation of unsuitable material and backfill with material acceptable to the Engineer under Section 203 – Excavation and Embankment. If no pay item exists, refer to Subsection 104.02 – Changes."

END OF SECTION 634