

1 **SECTION 630 – TRAFFIC CONTROL GUIDE SIGNS**

2
3 Make the following amendment to said Section:

4
5 **(I)** Amend **Section 630.02 - Materials**, by replacing lines 28 to 29 to read:

6
7 “Retroreflective sheeting shall conform to criteria listed in ASTM D 4956
8 for the applicable type and class, or as amended in accordance with Subsection
9 750.01 - Signs.”

10
11 **(II)** Amend **Section 630.04 - Measurement**, by replacing lines 204 to 221 to
12 read:

13
14 **“630.04 Measurement.** The Engineer will measure the number of route
15 markers assemblies as complete units of the type and design specified in the
16 proposal.

17
18 When the Engineer accepts an alternative design, the method of
19 measurement for the various contract items affected by the design shall be
20 identical with the various original contract items shown in the contract. The
21 Engineer will not measure the additional items that the Contractor requires for the
22 alternate design.

23
24 The Engineer will not measure removal and disposal and storing of existing
25 and temporary signs and markers that the Contractor will not incorporate in the
26 completed highway for payment.”

27
28 **(III)** Amend **630.05 – Payment** by revising lines 223 to 303 to read as follows:

29
30 **“630.05 Payment.** The Engineer will pay for route marker assemblies at the
31 contract price per each for the type and design specified complete in place.
32 Payment will be full compensation for the work prescribed in this section and the
33 contract documents.

34
35 The Engineer will not pay for removing and disposing or storing of existing
36 and temporary signs that the Contractor will not incorporate in the completed
37 highway separately. The Engineer will consider them incidental to the various
38 contract items.

39
40 The Engineer will not make payment other than those specified herein for
41 the construction of footings for overhead mounted expressway signs. The
42 Engineer will pay for the work, materials, tools, equipment and incidentals
43 required in the construction of the footings for overhead mounted expressway
44 signs under the following contract items:

- 46 (1) Footing Excavation. The Engineer will make payment for footing
47 excavation according to Section 204 – Excavation and Backfill for
48 Miscellaneous Facilities.
49
50 (2) Concrete. The Engineer will make payment for concrete in footings
51 according to Section 503 – Concrete Structures.
52
53 (3) Reinforcing Steel. The Engineer will make payment for reinforcing
54 steel according to Section 602 – Reinforcing Steel.
55

56
57 The Engineer will pay for the following pay items when included in the
58 proposal schedule:
59

60 Pay Item	61 Pay Unit
62 Type “A” Route Marker Assembly	63 Each
64 Type “B” Route Marker Assembly	65 Each

66 When the Engineer accepts an alternate design, the total amount paid
67 shall be full compensation for furnishing and installing materials and furnishing
68 equipment, tools, labors, and incidentals necessary to complete the work. The
69 Engineer will not make payment for additional materials, equipment, tools, labor
70 and other incidentals that might become necessary to complete the installation
71 due to the alternate design.
72
73
74
75

END OF SECTION 630