

1 **SECTION 641 – HYDRO-MULCH SEEDING**
2

3 Make the following amendments to said Section:
4

5 **(I)** Amend **Subsection 641.02(A) – Seed** by revising the section from line 22
6 to 24 to read:

7
8 “Seed shall comply with Hawaii Administrative Rules Title 4, Subtitle 6,
9 Chapter 67 Seed Rules; shall be certified for compliance by a Hawaii-
10 licensed seed dealer; and shall be purchased from that dealer. Seed shall
11 be a native plant species, for example, Pili (*Heteropogon contortus*) or
12 Mau’u ‘aki’aki (*Fimbristylis cymosa*), or other non-invasive grass.”
13

14 **(II)** Amend **Subsection 641.02(B) – Fertilizer** by revising the section from
15 line 33 to 36 to read:

16
17 **“(B) Fertilizer.** Proper fertilizer shall be used in hydro-mulch mix,
18 depending on condition of soil. Apply at rates and in amounts consistent
19 with manufacturer’s specifications. Contractor shall provide a Soil Analysis
20 Report, if requested by Engineer, and shall use report to determine
21 quantity and ratio of fertilizer for sustained growth of grass. Submit
22 recommendations from a licensed Landscape Architect when deviating
23 from the application rates and amounts above.”
24

25
26 **(III)** Amend **Subsection 641.03(A) – Seeding** by revising the first paragraph
27 from line 100 to 103 to read:

28
29 **“(A) Seeding.** Apply seeded mulch within the timeframe in Subsection
30 209.03(B) – Construction Requirements, if temporary stabilization will not
31 be utilized, after completion of slopes or portion of slope when exposed
32 face attains height of 15 feet. Notify Engineer not less than 24 hours
33 ahead of hydro-mulch seeding operation. Do not hydro-mulch until the
34 Engineer inspects and accepts areas for planting.”
35

36 **(IV)** Amend **Section 641.04 Measurement**, from line 173 to 174 to read as
37 follows:

38
39 **“641.04 Measurement.** The Engineer will measure hydro-mulch seeding
40 per square yard in accordance with the contract documents.”
41

42 **(V)** Amend **Section 641.05 Payment**, from line 176 to 185, to read as
43 follows:

44
45 **“641.05 Payment.** The Engineer will pay for the accepted hydro-mulch
46 seeding at the contract price per square yard. Payment will be full compensation
47 for the work prescribed in this section and the contract documents.
48

49 The Engineer will pay for the following pay item when included in the proposal
50 schedule:

51		
52	Pay Item	Pay Unit
53		
54	Hydro-mulch Seeding	Square Yard"
55		

56 **END OF SECTION 641**