

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	560-01-82M	1982	8	11

ROAD
CONSTRUCTION
NEXT ¾ MILE

REDUCED
SPEED
25
AHEAD

ROAD
CONSTRUCTION
1500 FT

SPEED
LIMIT
25

REDUCED
SPEED
15

ROAD
CONSTRUCTION
1000 FT

SPEED
LIMIT
15

REDUCED
SPEED
10

500
FEET

SPEED
LIMIT
10

500
FEET

ROAD
CONSTRUCTION
500 FT

END
CONSTRUCTION

END
CONSTRUCTION

LEGEND

- Sign
- Cone or Delineator
- ➡ Direction of traffic
- ☐ Police Officer / Flagman
- ☑ Amber Flasher

NOTES:

- The Contractor shall cover selected construction signs with the appropriate alternate signs (dashed lines) as directed by the Engineer, for use during non-working hours.
- All regulatory signs shall remain in use for the duration of the construction period, unless otherwise directed.
- All existing advisory speed signs within the construction zone shall be covered for the duration of the construction period.
- The limits of the construction zone shall include both bridges and shall be determined by the Engineer.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
LAND TRANSPORTATION FACILITIES DIVISION

TRAFFIC CONTROL PLAN

KAUAI BELT ROAD

Rehabilitation and Repairs to
Waipae Bridge and Waikoko Bridge

PROJ. NO. 560-01-82M

Not to Scale

SHEET NO. OF SHEETS

SURVEY PLOTTED BY	DATE
DRAWN BY	
DESIGNED BY	
CHECKED BY	
ORIGINAL PLAN	
NOTE BOOK	
No.	

