

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
KAUAI	HAWAII	560A-02-03	2010	7	32

POINT	HIGHWAY STA	O/S LT	POINT	HIGHWAY STA	O/S LT	POINT	HIGHWAY STA	O/S LT
R1	0+22.93	72.3'	M5	1+01.84	88.1'	M15	3+67.92	92.1'
R2	0+24.27	60.0'	M6	1+13.94	29.0'	M16	3+63.30	34.2'
R3	0+97.44	86.2'	M7	1+23.12	95.1'	M17	4+30.35	112.8'
R4	0+99.51	66.8'	M8	1+63.50	31.1'	M18	4+31.42	70.4'
R5	0+61.66	60.2'	M9	1+57.30	100.7'	M19	4+34.90	36.3'
R6	0+61.66	72.9'	M10	2+11.49	108.1'	P1	0+15.00	25.5'
M1	1+03.78	77.8'	M11	2+39.64	104.7'	P2	0+15.00	225.2'
M2	2+70.13	95.3'	M12	2+63.54	112.3'	P3	4+35.00	27.7'
M3	3+39.96	62.8'	M13	3+02.02	103.0'	P4	4+35.00	237.7'
M4	4+31.20	79.1'	M14	3+08.28	29.1'	P5	4+17.19	267.1'

**LEGEND FOR
AS-BUILT POSTINGS**



 Squiggly line for as-built deletion
 Double line for as-built deletion
 Text for as-built posting

Scale slope within
project limits —

~~Right-of-Way~~

— Perform boulder demolition as indicated on Sheet 15; a max of 50 trees may be identified by the Engineer to remain in place; clear remaining trees and surface vegetation within wire mesh limits; dress slope to provide a smooth surface; hydro-mulch seed; install permanent erosion control mat; provide tree protection per manufacturer's recommendation for those trees identified to remain; and construct anchored wire mesh (Areas 1, 2, and 3)

Note:

1. Upon determination by the Engineer that suitable embedment length for anchor in Area 1 has been reached at shallower depths than 35 feet, the Engineer may direct the Contractor to limit the anchor embedment at 20 feet for any anchor location. In such case, the Contractor shall credit the State for anchor and installation work not performed, in accordance with the unit prices identified in the proposal schedule or as negotiated with the Engineer.

GRAPHIC SCALE

20 0 20
SCALE: 1"=20'

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

SITE PLAN

KUHIO HIGHWAY SLOPE STABILIZATION
VICINITY OF HANAIEI BRIDGE
PROJECT NO. 560A-02-03

Scale: As Noted Date: July 2009
SHEET No. 1 OF 1 SHEETS

"AS-BUILT"

1