

1 **SECTION 508 – CEMENT RUBBLE MASONRY**
2

3 Make the following amendments to said Section:
4

5 **(I) Amend 508.02 Materials** by adding the following paragraph after line 33
6 to read as follows:
7

8 “Color and Pattern shall be determined by the Engineer. The Contractor shall
9 submit six copies of the product data for approval by the Engineer. Prior to
10 constructing the permanent CRM wall, the Contractor shall produce a 3 feet by 3
11 feet sample specimen for approval by the Engineer at no increase in contract price
12 and contract time. Sample specimen shall replicate the appearance of the face
13 stones in the permanent wall.”
14

15 **(II) Amend 508.04 Measurement** to read as follows:
16

17 **“508.04 Measurement.** The quantity to be paid for cement rubble masonry is the
18 quantity shown in the proposal schedule. The contract quantity will be adjusted for
19 authorized changes that affect the quantity or for errors made in computing this
20 quantity. If there is evidence that a quantity specified as a contract quantity is
21 incorrect, submit calculations, drawings, or other evidence indicating why the
22 quantity is in error and request, in writing, that the quantity be adjusted.”
23

24 **(III) Amend 508.05 Payment** to read as follows:
25

26 **“508.05 Payment.** The Engineer will pay for the accepted cement rubble masonry
27 at the contract unit price per pay unit, as shown in the proposal schedule. Payment
28 will be full compensation for the work prescribed in this section and the contract
29 documents.
30

31 The Engineer will pay for the following pay item when included in the
32 proposal schedule:
33

34 Pay Item	35 Pay Unit
36 Cement Rubble Masonry _____	37 Cubic Yard”

38
39
40

END OF SECTION 508