

1 **SECTION 603 – CULVERTS AND STORM DRAINS**

2
3 Make the following amendment to said Section:

4
5 **(I) Amend Subsection 603.03 (C)(1) Culverts**, by revising lines 106 to 108 to
6 read as follows:

7
8 “Spacing between multi-barrel circular culverts shall be a minimum of 18
9 inches or 0.5 diameter of culvert, whichever is greater. The minimum spacing
10 shall be 1 foot when placing controlled low strength material (CLSM) as backfill.”

11
12
13
14
15
16
17 **END OF SECTION 603**