

## SECTION 629 - PAVEMENT MARKINGS

Make the following amendments to said Section:

(I) Amend **Subsection 629.03(B) – Temporary Pavement Markings** by revising the third paragraph from line 62 to 63 to read:

“Maintain and replace temporary pavement markings, flexible delineators, and barricades. ”

(II) Amend **Table 629.03 – 1 – Temporary Pavement Markings** to read as follows:

“TABLE 629.03-1 TEMPORARY PAVEMENT MARKINGS	
TYPE	PAVEMENT MARKINGS
Passing Permitted - Both Sides	Single 4-inch yellow stripe 5 feet in length spaced 20 feet on center with Type D markers spaced 40 feet on center and located on center of 5-foot length of stripe.
Passing Prohibited - Both Sides	Double solid 4-inch yellow stripes with Type D markers placed 20 feet on center on one of 4-inch yellow stripes selected by the Engineer.
Passing Permitted - One Side Only	Single continuous 4-inch yellow stripe with Type D markers placed on stripe 20 feet on center on no-passing side and single 4-inch yellow stripes 5 feet in length spaced 20 feet on center on passing side.
Lane Lines - Lane Changing Permitted	Single 4-inch yellow or white stripe 5 feet in length spaced 20 feet on center with Type C or Type D markers spaced 40 feet on center.
Lane Lines - Lane Changing Prohibited	Double solid 4-inch white stripes with Type C markers placed 20 feet on center on one of the 4-inch white stripes selected by the Engineer.
Crosswalk	Two 12-inch white transverse lines spaced 8 feet on center or as ordered by the Engineer.
Stop Line	Single 12-inch white transverse line.
<b>Note:</b> Paint may be used for temporary markings in areas where final paving is not complete.”	

(III) Amend **629.04 – Measurement** by revising lines 292 to 294 to read as follows:

19 **"629.04 Measurement.**

- 20
- 21 (A) The Engineer will measure thermoplastic and preformed pavement
- 22 marking tape per linear foot in accordance with the contract
- 23 documents. The longitudinal pavement markings will be measured per
- 24 linear foot as a single stripe for the width specified in the contract and
- 25 in the proposal. The Engineer will include the longitudinal gaps for skip
- 26 striping, up to thirty (30) feet long, in the measurement.

27

28 The Engineer will not measure temporary pavement markings

29 including flexible delineator posts with reflector markers or Type I

30 Barricades and temporary signs installed for the longitudinal guidance

31 of public traffic over reconstructed areas, cold planed surfaces, newly

32 paved surfaces or other unmarked or scarified areas for payment.

33

34 The Contractor shall consider the work required for the removal of

35 pavement markings incidental to the various contract items, except as

36 provided in the proposal or elsewhere in the contract. If the contract

37 stipulates that the Engineer will make payment for the removal of

38 pavement markings, the Engineer will measure the removal of

39 pavement markings.

- 40
- 41 (B) The Engineer will measure the pavement markers per each for the
- 42 types shown in the proposal.

- 43
- 44 (C) The Engineer will measure the painted stripes that are twelve (12)
- 45 inches wide or less as a single stripe. The Engineer will measure the
- 46 painted stripes over twelve (12) inches wide as two (2) stripes. The
- 47 Engineer will measure the double stripes that are twelve (12) inches or
- 48 less in total width including the transverse space between the stripes
- 49 as a single stripe.

50

51 The Engineer will measure the transverse markings by the linear

52 foot, per lane, per each or per gallon according to the contract.

- 53
- 54 (IV) Amend **629.05 – Payment** by revising lines 296 to 330 to read as follows:

55

56 **"629.05 Payment.**

- 57
- 58 (A) The Engineer will pay for thermoplastic and preformed pavement
- 59 marking tape at the contract price per linear foot or on a lump sum
- 60 basis according to the contract, complete in place, including primers.

61

62 The contract unit price paid shall be full compensation for furnishing

63 labors, materials, tools, equipment and incidentals and for doing the

64 work involved in furnishing and installing pavement markings complete

65 in place according to the contract.

The Engineer will not pay for the temporary pavement markings including flexible delineator posts with reflector markers or Type I Barricades and temporary signs installed for the longitudinal guidance of public traffic over reconstructed areas, cold planed surfaces, newly paved surfaces or other unmarked or scarified areas for payment if not shown in the proposal separately. The Engineer will consider them incidental to the various contract items.

(B) The Engineer will pay for the various types of pavement markers at the contract price per each or on a lump sum basis according to the contract, complete in place, including adhesives.

(C) The Engineer will pay for painted pavement striping at the contract price per linear foot or on a lump sum basis according to the contract.

The Engineer will pay for the following pay items when included in the proposal schedule:

Pay Item	Pay Unit
_____ - Inch Pavement Striping (Type ____ Tape or Thermoplastic)	Linear Foot
Type ____ Pavement Marker	Each

**END OF SECTION 629”**