

SECTION 645 – WORK ZONE TRAFFIC CONTROL

Make the following amendments to said Section:

(I) Amend **645.02 – Materials** by revising lines 39 to 48 to read as follows:

“Submit at least 30 working days before work starts, 3 sets of FHWA approval letters certifying compliance with AASHTO Manual for Assessing Safety Hardware (MASH) for signs, sign supports, barricades, delineators, cones, vertical panels, concrete barriers with MASH end treatments, and other traffic control devices.

Furnish to Engineer at least 30 working days before work starts, 3 sets of self-certified MASH compliant letter from vendor for each type of Category 1 traffic control device, as defined in MASH, including single-piece traffic cone, single-piece drum, tubular marker, and delineator.

Use of signs, sign supports, barricades, delineators, cones, vertical panels, and other traffic control devices that are not certified to be MASH compliant shall not be used unless a request for a waiver is submitted in writing and a written waiver is given by the Engineer.”

(II) Amend **645.03 - Construction** by adding the following after the sentence on line 61:

“In addition to the traffic control plans, furnish, install and maintain two (2) electronic message boards (126 inches wide and 76 inches high), locations to be determined by the Engineer.”

(III) Amend **Subsection 645.03(F) Lane Closures** by revising lines 248 to 282 to read as follows:

“(F) Lane Closures. Lane closures as shown in the traffic control plans will be allowed:

Kuhio Highway (Ohiki Road to Hanalei Plantation Road)

Sunday: 11:00 p.m. to Midnight

Weekdays: Midnight to 5:30 a.m. and 11:00 p.m. to Midnight (excluding Friday Evening). No closures are allowed Friday Evening.

Night work and night closures will not be allowed during the seabird fallout season period (September 15 to December 15).

Keep lanes open to traffic and allow flow at posted speed limit during non-working hours.

Exceptions to lane closure hours specified require written acceptance by the Engineer. No increase in contract price or contract time will be given for lane closure restrictions specified.

The Contractor shall coordinate lane closures with adjacent projects at no increase to the contract price or contract time.

Exceptions to the lane closure hours specified shall require a written request 10 working days for the Engineer's approval prior to any adjustments specified."

(IV) Amend **Subsection 645.03(G) Advisory Signs** by revising lines 314 to 324 to read as follows:

"(G) Advisory Signs are not required for this project."

(V) Amend **Subsection 645.03(H) Advertisement** by revising lines 391 to 392 to read as follows:

" Place advertisement for three consecutive days and within one week before traffic pattern changes, in publication as ordered by the Engineer. In lieu of the advertisement(s), the Engineer may substitute the use of two portable changeable message boards and accessories at no additional cost for three days for each required advertisement."

(VI) Amend **645.05 – Payment** by revising lines 405 to 428 to read as follows:

"645.05 Payment. The Engineer will pay for the accepted traffic control, additional police officers, and additional traffic control devices, and additional advertisements at the contract price per pay unit, as shown in the proposal schedule. Payment will be full compensation for the work prescribed in this section and the contract documents.

The Engineer will pay for the following pay items when included in the proposal schedule:

Pay Item	Pay Unit
Traffic Control _____	Lump Sum
Additional Police Officers, Additional Traffic Control Devices, and Additional Advertisements	Force Account

94
95
96
97
98
99
100
101
102
103
104
105
106

An estimated amount for the force account may be allocated in the proposal schedule under “Additional Police Officers, Additional Traffic Control Devices, and Additional Advertisements”, but the actual amount to be paid will be the sum shown on the accepted force account records, whether this sum be more or less than the estimated amount allocated in the proposal schedule.

The Engineer will not pay for request submittals. The Engineer will not consider claims for additional compensation of late submittals or requests by Contractor.”

END OF SECTION 645