

1                                   **SECTION 645 - WORK ZONE TRAFFIC CONTROL**

2  
3    Make the following amendments to said Section:

4  
5    **(I)**     Amend **645.03 Construction** from line 64 to 66 to read as follows:

6  
7            "Furnish two flaggers or police officers for each location that requires work  
8            zone traffic control. If TCP is included in the contract documents, furnish  
9            number of flaggers or police officers indicated in TCP."

10  
11   **(II)**    Amend **645.03 (B) Construction Signs** from line 162 to 169 by changing all  
12            references to "Construction Signs" to read "**Work Zone Signs**".

13  
14   **(III)**   Amend **Subsection 645.03 Construction** by adding this paragraph after line  
15            170 to read as follows:

16  
17            **"(1) Covers.** Use sign covers when existing signs confuse the public or  
18            are in conflict with TCP signs installed. Sign covers shall be commercially  
19            manufactured and accepted by the Engineer before use. Sign covers shall at  
20            all times and under all conditions not allow any portion of the sign being  
21            covered to be visible. If more than one side of the sign has words or symbols  
22            cover all sides of the sign until needed. "Homemade" or "field made" covers  
23            shall not be used. Covering of sign identification markings are not required if  
24            that is the only markings on that side of the sign. Sign covers shall be  
25            maintained.

26  
27            Removal of the existing sign in lieu of the use of sign covers may be  
28            acceptable to the Engineer provided the previously removed existing sign is  
29            immediately reinstalled when directed. Removal of existing post(s) and  
30            mounting hardware is required if not used to mount the new TCP sign. New  
31            mounting hardware shall be used to mount the TCP signs if the existing  
32            hardware is in an unacceptable condition in the opinion of the Engineer. In  
33            addition, should the sign or post during storage, in the opinion of the  
34            Engineer, become unacceptable or lost or stolen the Contractor shall replace  
35            the sign or post with a new sign or post. Use new hardware to reinstall the  
36            sign regardless whether it is an existing sign or new."

37  
38   **(II)**    Amend **Subsection 645.03 (F) Lane Closures** Line 253 by changing "Oahu"  
39            to "Kauai".

40  
41   **(III)**   Amend **Subsection 645.03 (G) Advisory Signs** from Line 314 to Line 324 to  
42            read as follows:

43  
44            **"(G) Advisory Signs.** Advisory signs are not required for this project."

(IV) Amend **Subsection 645.03 (H) Advertisement** from Line 391 to Line 392 to read as follows:

“Place advertisement for three (3) consecutive days and within one week before traffic pattern changes, in publication as ordered by the Engineer. In lieu of the advertisement(s), the Engineer may substitute the use of two portable changeable message boards and accessories at no additional cost for three (3) days for each required advertisement.”

(V) Amend **Subsection 645.04 - Measurement** from line 394 to line 403 to read as follows:

**“645.04 Measurement.**

(A) Traffic control as specified in Subsection 645.03 – Construction including sign covers and the initial advertisement(s) will be measured on contract lump sum basis. Measurement for payment will not apply.

(B) The Engineer will measure additional police officers, additional traffic control devices, and additional advertisements, if ordered by the Engineer, on a force account basis, in accordance with Subsection 109.06 – Force Account Provisions and Compensation.’

(VI) Amend **Subsection 645.05 - Payment** from lines 405 to 428 to read:

**“645.05 Payment.** The Engineer will pay for the accepted traffic control, additional police officers, and additional traffic control devices, and additional advertisements at the contract price per pay unit, as shown in the proposal schedule. Payment will be full compensation for the work prescribed in this section and the contract documents.

The Engineer will pay for the following pay items when included in the proposal schedule:

<b>Pay Item</b>	<b>Pay Unit</b>
Traffic Control	Lump Sum
Additional Police Officers, Additional Traffic Control Devices, and Additional Advertisements	Force Account

An estimated amount for the force account may be allocated in the proposal schedule under “Additional Police Officers, Additional Traffic Control Devices, and Additional Advertisements”, but the actual amount to be paid will be the sum shown on the accepted force account records, whether this sum be more or less than the estimated amount allocated in the proposal schedule.

96           The Engineer will not pay for request submittals. The Engineer will not  
97 consider claims for additional compensation of late submittals or requests by  
98 Contractor.”  
99

100  
101  
102

**END OF SECTION 645**