SECTION 503 – CONCRETE STRUCTURES

Make the following amendments to said Sections:

(I) Amend **503.02 Materials.** By adding following paragraph after line 34

"Include professional grade liquid coloring admixture to achieve brown colored concrete or as close to brown as feasible. Suggest BASF Master Builders Solution "Warm Earth 1508" or an equivalent.

Provide a colored test slab or panel, minimum 6 inch x 6 inch using concrete of the same design mix for Engineer's review and approval.

The test slab or panel is considered incidental work and will not be paid separately."

(II) Amend **Section 503.04 Measurement**, from line 1201 to 1204 to read as follows:

"**503.04 Measurement.** The Engineer will measure concrete swale per linear foot in accordance with the contract documents."

(III) Amend **Section 503.05 Payment**, from line 1206 to 1215 to read as follows:

"**503.05 Payment.** The Engineer will pay for the accepted concrete swale at the contract price per linear foot. Payment will be full compensation for the work prescribed in this section and the contract documents.

The Engineer will pay for the following pay item when included in the proposal schedule:

Pay Item	**Pay Unit**
Concrete Swale _____	Linear Foot"

END OF SECTION 503