

**SECTION 703 – AGGREGATES**

Make the following amendments to said Section:

**(I) Amend TABLE 703.01-3 FINE AGGREGATE GRADING REQUIREMENTS, HAWAII AND KAUAI to read as follows:**

“

<b>TABLE 703.01-3 - FINE AGGREGATE GRADING REQUIREMENTS, HAWAII AND KAUAI</b>		
<b>Sieve Sizes</b>	<b>Percent Passing by Weight</b>	
	<b>Calcareous Sand</b>	<b>Crusher Screenings</b>
3/8 Inch	100	100
No. 4	95 – 100	95 - 100
No. 8	-	50 - 85
No. 16	-	32 - 60
No. 30	-	-
No. 50	-	15 - 30
No. 100	0 – 5	5 - 20

“

**END OF SECTION 703**