

## SECTION 407 – TACK COAT

Make the following amendment to said Section:

- (I) Amend **Section 407.03(D) – Application of Tack Coat**, from lines 63 to 72 to read:

“Apply tack coat on existing asphalt or concrete surface, or both, to be overlaid by HMA or PMA course. Once water has evaporated from asphalt emulsion, tack coat is said to have set. Place HMA or PMA overlay after tack coat has set and within four hours of application. For multiple lift construction of HMA or PMA, tack coat application will not be waived. Remove all deleterious material to bonding before applying the tack coat to the entire surface to receive the next lift.

Before placing HMA or PMA course, apply tack coat to contact surfaces of curbs, gutters, manholes, other structures, vertical faces of existing pavements, and exposed transverse and longitudinal edges of each course. Apply tack coat on all surfaces that will have an asphalt pavement placed on it in a uniform, full coverage manner, e.g., no visible streak, holidays in the application, no differences in the application rate, i.e., the thickness of the tack coat. The exception to this requirement shall be surfaces that will have pavement joint adhesive applied to it which shall not require any tack coat.”

END OF SECTION 407