

1 **SECTION 634 – PORTLAND CEMENT CONCRETE SIDEWALKS**

2
3 Make the following amendment to said Section:

4
5 **(I) Amend Section 634.02 - Materials** by adding the following paragraph after
6 line 8:

7
8 “Include professional grade liquid coloring admixture to achieve brown
9 colored concrete or as close to brown as feasible. Suggest BASF
10 Master Builders Solution “Champagne MC2510” or an equivalent.

11
12 Provide a colored test slab or panel, minimum 2 feet x 2 feet using
13 concrete of the same design mix for Engineer’s review and approval.

14
15 The test slab or panel is considered incidental work and will not be
16 paid separately.”

17
18 **(II) Amend Section 634.03 (F) - Finishing** by adding the following after line 32:

19
20 “Some portland cement concrete sidewalk as shown on the plans shall be
21 textured with an ADA compliant concrete stamp to create a more natural-looking
22 finish. Provide a colored test slab or panel, minimum 2 feet x 2 feet using
23 concrete of the same design mix for Engineer’s review and approval.”

24
25 **(III) Amend Section 634.04 - Measurement** by replacing lines 60 to 61 to read:

26
27 “**634.04 Measurement.** The Engineer will measure Portland cement concrete
28 sidewalks by the square yard of finished surface.”

29
30 **(IV) Amend Section 634.05 – Payment** by replacing lines 62 to 72 to read:

31
32 “**634.05 Payment.** The Engineer will pay for the accepted quantities of
33 Portland cement concrete sidewalk at the contract unit price per square yard
34 complete in place price as shown in the proposal.

35
36 Payment will be full compensation for work prescribed in this section and
37 contract documents.

38
39 The Engineer will pay for following pay item when included in proposal
40 schedule:

41

| 42 Pay Item | Pay Unit |
|--|-------------|
| 43 | |
| 44 Portland Cement Concrete Sidewalk, 4” Depth | Square Yard |
| 45 | |
| 46 Portland Cement Concrete Sidewalk, 6” Depth | Square Yard |
| 47 | |

48 The Engineer will pay for excavation of unsuitable material and backfill
49 with material acceptable to the Engineer under Section 203 – Excavation and
50 Embankment. If no pay item exists, refer to Subsection 104.02 – Changes.”
51
52
53

END OF SECTION 634