

1 Make the following section a part of the Standard Specifications:

2
3 **"SECTION 212 — ARCHAEOLOGICAL MONITORING**

4
5 **212.01 Description.** This section describes the monitoring of construction
6 activity for archaeological items at the locations shown on the plans and as
7 directed by the Engineer.

8
9 An archaeological monitoring plan has been submitted and a verbal
10 concurrence provided by the State Department of Land and Natural Resources,
11 State Historic Preservation Division. Copies of the approved monitoring plan are
12 on file at the office of the Engineer.

13
14 **212.02 Materials (Not Used).**

15
16 **212.03 Construction.** In addition to the requirements of Section 107.13
17 (B) – Archaeological, Historical, and Burial Sites, the Contractor shall obtain the
18 services of a qualified Archaeologist or firm to inspect the site prior to clearing
19 and grubbing and to monitor construction activities during clearing and grubbing
20 and excavation operations for historic remains such as artifacts, burials and
21 concentrations of shell or charcoal.

22
23 If remains are found, work shall cease in the immediate vicinity of the find
24 and the area shall be protected from further damage. The Contractor shall
25 immediately contact the State Historic Preservation Division (692-8015), which
26 will assess the significance of the find and recommend appropriate mitigation
27 measures to be implemented, if necessary.

28
29 **212.04 Measurement.** Archaeological monitoring as directed by the
30 Engineer, including any remedial measures that may be required, will be
31 measured on a force account basis in accordance with Subsection 109.06 –
32 Force Account Provisions and Compensation.

33
34 **212.05 Payment.** The Engineer will pay for the accepted pay item(s)
35 approved by the Engineer and as listed below on a force account basis in
36 accordance with Subsection 109.06 – Force Account Provisions and
37 Compensation.

38
39

Pay Item	Pay Unit
Archaeological Monitoring	Force Account

40
41
42
43 The Engineer will not pay for work required that is solely for Contractor's
44 convenience or due to the Contractor's negligence, carelessness or failure to
45 properly monitor excavation activities."

46
47 **END OF SECTION 212**